

# Construction Estimate — Breakdown

5213 Call Place SE, Washington DC 20019 · New-construction detached group home / residential care (R-2), Type IIIB · Cellar + 3 stories · 5,920 GSF · 8 BR / 14 beds / 7 baths / 1 commercial kitchen / 1 elevator  
Priced through the Kealee catalogue (packages/estimating, DC factor 1.15) · Markups OH 12% / Profit 15% / Contingency 7% · Generated 2026-07-14

**Basis of estimate — measured from the permit set (28 sheets). 84.8% of direct cost is dimensioned** (measured off schedules/plans or calculated from drawing dimensions); every line below lists its dimensional basis and sheet. The remaining 15% is scope that cannot be measured from this set: Division 01 general conditions (time/effort-based), utility service laterals (no civil sheet), and security (not designed). Drawings stamped NOT FOR PERMITTING — estimation only. Persisted to Postgres (quick\_estimates + estimate\_line\_items).

## Recommended target: \$301/SF–\$300/SF (\$1,780,237–\$1.78M base building)

The \$170/SF (\$1,006,400) target is **not achievable** for a cellar+3, elevatored, sprinklered, masonry R-2 group home in DC without deleting code-required life-safety, accessibility, or structural scope.

## Executive summary — scenario comparison

| SCENARIO             | TOTAL (EXCL. ELEVATOR + KITCHEN EQUIP) | \$/GSF   | \$/BED    | VS \$170/SF |
|----------------------|----------------------------------------|----------|-----------|-------------|
| A — Catalogue Market | \$2,380,707                            | \$402/SF | \$170,050 | +137%       |
| B — Value-Engineered | \$2,067,116                            | \$349/SF | \$147,651 | +105%       |
| C — Minimum Viable   | \$1,780,237                            | \$301/SF | \$127,160 | +77%        |
| Target               | \$1,006,400                            | \$170/SF | \$71,886  | —           |

**CTC cross-check:** the same takeoff priced against the Construction Task Catalog (data/ctc) totals **\$2,234,427 (\$377/SF)** — within **-6.1%** of Scenario A. Only **45.7%** of direct cost maps to a real CTC task (41-task sample); the rest is allowance.  
**Labor wage schedule:** apprentice \$55 · journeyman \$85 · master \$124/hr. Labor = labor-hours × crew rate — general trades **\$73/hr** (60% journeyman + 40% apprentice); licensed MEP/fire **\$87.25/hr** (25% master + 50% journeyman + 25% apprentice (Div 21/22/23/26/27-28)). Div 01 general conditions salaried; subcontractor lump sums keep quoted value.

## Scenario A — cost build-up

|                                        |             |           |               |             |
|----------------------------------------|-------------|-----------|---------------|-------------|
| DIRECT CONSTRUCTION                    | MATERIAL    | LABOR     | SUBCONTRACTOR | LABOR-HOURS |
| \$1,735,555                            | \$466,908   | \$657,321 | \$578,606     | 8,545       |
| Direct construction                    | \$1,735,555 |           |               |             |
| GC overhead (12%)                      | \$208,267   |           |               |             |
| GC profit (15%)                        | \$260,333   |           |               |             |
| Contingency (7%)                       | \$121,489   |           |               |             |
| Bonds & insurance (1.5%)               | \$33,062    |           |               |             |
| Permit allowance (DCRA)                | \$22,000    |           |               |             |
| TOTAL (excl. elevator + kitchen equip) | \$2,380,707 |           |               |             |

## CSI division summary

| DIV                        | DESCRIPTION                        | SCENARIO A         | SCENARIO B         | SCENARIO C         | A LAB-HRS    |
|----------------------------|------------------------------------|--------------------|--------------------|--------------------|--------------|
| 01                         | General Conditions                 | \$252,495          | \$222,195          | \$191,896          | 2,043        |
| 02                         | Existing Conditions                | \$32,848           | \$28,906           | \$24,964           | 56           |
| 03                         | Concrete                           | \$143,985          | \$126,706          | \$109,428          | 501          |
| 04                         | Masonry                            | \$25,144           | \$22,127           | \$19,109           | 150          |
| 05                         | Metals (structural steel)          | \$55,466           | \$48,810           | \$42,154           | 192          |
| 06                         | Wood, Plastics & Rough Carpentry   | \$159,625          | \$140,470          | \$121,315          | 889          |
| 07                         | Thermal, Moisture & Exterior       | \$113,419          | \$99,809           | \$86,199           | 585          |
| 08                         | Openings                           | \$63,921           | \$56,250           | \$48,580           | 229          |
| 09                         | Finishes                           | \$246,524          | \$216,941          | \$187,358          | 2,200        |
| 10                         | Specialties                        | \$13,561           | \$11,934           | \$10,307           | 47           |
| 12                         | Furnishings (built-in)             | \$21,734           | \$19,126           | \$16,518           | 84           |
| 21                         | Fire Suppression                   | \$53,980           | \$47,502           | \$41,025           | 0            |
| 22                         | Plumbing                           | \$104,100          | \$91,608           | \$79,116           | 385          |
| 23                         | HVAC                               | \$122,549          | \$107,843          | \$93,137           | 352          |
| 26                         | Electrical                         | \$140,745          | \$123,855          | \$106,966          | 570          |
| 27/28                      | Communications & Electronic Safety | \$35,862           | \$31,558           | \$27,255           | 20           |
| 31                         | Earthwork                          | \$55,343           | \$48,702           | \$42,061           | 187          |
| 32                         | Exterior Improvements              | \$32,256           | \$28,385           | \$24,515           | 55           |
| 33                         | Utilities                          | \$62,000           | \$54,560           | \$47,120           | 0            |
| <b>Direct construction</b> |                                    | <b>\$1,735,555</b> | <b>\$1,527,289</b> | <b>\$1,319,022</b> | <b>8,545</b> |

## Excluded-cost schedule (NOT in any total above — owner procures separately)

### Elevator — \$142,000 allowance

|                                              |                  |
|----------------------------------------------|------------------|
| Passenger elevator equipment — 3,500# (A001) | \$72,000         |
| Elevator cab, doors & landing entrances      | \$22,000         |
| Rails, controls & fixtures                   | \$18,000         |
| Elevator installation labor                  | \$24,000         |
| Testing, inspection & DCRA certification     | \$6,000          |
| <b>Elevator total</b>                        | <b>\$142,000</b> |

Included in base building: elevator pit (Div 03), hoistway shaft framing + 2-hr rated enclosure (Div 06), power rough-in & disconnect (Div 26).

### Commercial kitchen equipment — \$120,500 allowance

|                                              |          |
|----------------------------------------------|----------|
| Type I exhaust hood package (KEF-1)          | \$14,000 |
| Hood fire suppression (Ansul)                | \$6,500  |
| Make-up air unit MAU-1 (if equipment-scoped) | \$12,000 |
| Walk-in refrigerator (A001)                  | \$11,000 |
| Walk-in freezer (A001)                       | \$13,000 |
| Cooking equipment (double oven + line)       | \$28,000 |
| Commercial dishwasher                        | \$9,000  |
| Stainless prep tables, sinks, shelving       | \$12,000 |

|                                                |                  |
|------------------------------------------------|------------------|
| Loose / owner-furnished food-service equipment | \$15,000         |
| <b>Kitchen equipment total</b>                 | <b>\$120,500</b> |

Included in base building: kitchen plumbing/gas rough-in (Div 22), electrical rough-in (Div 26), hood curb + exhaust/MUA ductwork (Div 23), kitchen wall/floor/ceiling finishes (Div 09).

**Owner cash-flow summary (Scenario A base building)**

|                    |                 |                  |                  |                  |
|--------------------|-----------------|------------------|------------------|------------------|
| BASE BUILDING      | PER GSF         | PER BED (14)     | PER BEDROOM (8)  | PER BATHROOM (7) |
| <b>\$2,380,707</b> | <b>\$402/SF</b> | <b>\$170,050</b> | <b>\$297,588</b> | <b>\$340,101</b> |

|                                                             |                    |
|-------------------------------------------------------------|--------------------|
| Base-building construction (excl. elevator + kitchen equip) | <b>\$2,380,707</b> |
| Separate elevator allowance                                 | \$142,000          |
| Separate kitchen-equipment allowance                        | \$120,500          |
| <b>All-in incl. excluded allowances</b>                     | <b>\$2,643,207</b> |

## Detailed line-item breakdown — Scenario A

shaded rows = labeled temporary allowance (no catalogue assembly). Code column shows the Kealee catalogue code or ALLOWANCE. Sub-Eq/u = subcontractor or equipment unit cost.

| DIVISION 01 — General Conditions · \$252,495      |                   |          |                                           |       |      |         |         |      |           |           |           |
|---------------------------------------------------|-------------------|----------|-------------------------------------------|-------|------|---------|---------|------|-----------|-----------|-----------|
| ITEM                                              | CODE              | METHOD   | DIMENSION BASIS [SHEET]                   | QTY   | UNIT | MAT \$  | LAB-HRS | RATE | LABOR \$  | SUB-EQ \$ | TOTAL     |
| Project Management – Weekly                       | GEN-PM-WEEKLY     | CALC     | 12-mo schedule                            | 52    | each | \$0     | 416     | sal. | \$41,860  | —         | \$41,860  |
| Site superintendent (12 mo)                       | ALLOWANCE         | ASSUMED  | 12-mo build                               | 12    | mo   | \$0     | 1,520   | sal. | \$114,000 | —         | \$114,000 |
| Mobilization / demobilization                     | ALLOWANCE         | ASSUMED  |                                           | 1     | ls   | \$0     | 0       | sal. | \$0       | \$18,000  | \$18,000  |
| Temporary Power                                   | GEN-TEMP-POWER    | CALC     | monthly                                   | 12    | each | \$5,796 | 48      | sal. | \$4,830   | —         | \$10,626  |
| Temporary water / heat / enclosure                | ALLOWANCE         | ASSUMED  |                                           | 12    | mo   | \$0     | 0       | sal. | \$0       | \$10,200  | \$10,200  |
| Portable Toilet – Monthly                         | GEN-PORT-TOILET   | CALC     |                                           | 12    | each | \$2,536 | 0       | sal. | \$0       | —         | \$2,536   |
| Safety / OSHA / PPE program                       | ALLOWANCE         | ASSUMED  |                                           | 1     | ls   | \$0     | 0       | sal. | \$0       | \$14,000  | \$14,000  |
| Dumpster – 30 Yard                                | GEN-DUMP-30       | CALC     |                                           | 10    | each | \$7,245 | 0       | sal. | \$0       | —         | \$7,245   |
| Final Construction Cleanup                        | GEN-CLEANUP-FINAL | MEASURED | GSF 5,920 [A001-A002]                     | 5,920 | sqft | \$1,776 | 59      | sal. | \$3,078   | —         | \$4,854   |
| Testing & special inspections (Type IIIB + steel) | ALLOWANCE         | ASSUMED  | [A000/S101]                               | 1     | ls   | \$0     | 0       | sal. | \$0       | \$18,000  | \$18,000  |
| Property Survey                                   | GEN-SURVEY        | CALC     |                                           | 1     | each | \$725   | 0       | sal. | \$0       | —         | \$725     |
| Structural Engineering                            | GEN-ENGINEER      | CALC     | [S101]                                    | 1     | each | \$1,449 | 0       | sal. | \$0       | —         | \$1,449   |
| Closeout / as-builts / O&M / commissioning        | ALLOWANCE         | ASSUMED  |                                           | 1     | ls   | \$0     | 0       | sal. | \$0       | \$9,000   | \$9,000   |
| DIVISION 02 — Existing Conditions · \$32,848      |                   |          |                                           |       |      |         |         |      |           |           |           |
| ITEM                                              | CODE              | METHOD   | DIMENSION BASIS [SHEET]                   | QTY   | UNIT | MAT \$  | LAB-HRS | RATE | LABOR \$  | SUB-EQ \$ | TOTAL     |
| Clearing & site preparation                       | ALLOWANCE         | CALC     | lot 4,000 SF (20'×100' / 40'×100') [A000] | 4,000 | sqft | \$0     | 32      | \$73 | \$2,336   | \$9,600   | \$11,936  |
| Erosion & sediment control (DOEE/SWM)             | ALLOWANCE         | CALC     | lot perimeter silt fence ~280 LF [A000]   | 280   | lf   | \$2,688 | 24      | \$73 | \$1,744   | \$4,480   | \$8,912   |
| New rear areaway excavation/retaining             | ALLOWANCE         | MEASURED | rear areaway shown (scope note) [A000]    | 1     | ls   | \$0     | 0       | \$73 | \$0       | \$12,000  | \$12,000  |

| DIVISION 03 — Concrete · \$143,985             |                  |          |                                                     |       |      |          |         |      |          |           |          |
|------------------------------------------------|------------------|----------|-----------------------------------------------------|-------|------|----------|---------|------|----------|-----------|----------|
| ITEM                                           | CODE             | METHOD   | DIMENSION BASIS [SHEET]                             | QTY   | UNIT | MAT \$   | LAB-HRS | RATE | LABOR \$ | SUB-EQ \$ | TOTAL    |
| Drilled piers 18"Ø×30" (4-#5 vert, #3 ties)    | ALLOWANCE        | MEASURED | 18"Ø×30" deep × ~10 at HSS cols/perimeter [S100]    | 10    | ea   | \$4,125  | 0       | \$73 | \$0      | \$12,375  | \$16,500 |
| Grade beams / foundation wall — 8" CIP         | ALLOWANCE        | CALC     | P176 × 9' cellar = 1,584 SF [S100]                  | 1,584 | sqft | \$13,464 | 144     | \$73 | \$10,488 | \$29,621  | \$53,573 |
| Concrete Pour — 4\                             | CONC - POUR - 4  | MEASURED | 4" SOG, 24×~62 = 1,480 SF [S100]                    | 1,480 | sqft | \$8,036  | 59      | \$73 | \$4,322  | —         | \$12,358 |
| Wire Mesh Placement                            | CONC - MESH      | MEASURED | W2.9×W2.9 WWF over slab area [S100]                 | 1,480 | sqft | \$888    | 15      | \$73 | \$1,080  | —         | \$1,968  |
| Elevator pit (excavate/form/pour/waterproof)   | ALLOWANCE        | MEASURED | 7'-9"×7'-9" hoistway pit [A001]                     | 1     | ea   | \$0      | 0       | \$73 | \$0      | \$9,500   | \$9,500  |
| Exterior concrete (rear areaway, stoop, steps) | ALLOWANCE        | MEASURED | rear areaway + front entry slab ~400 SF [A000/S100] | 400   | sqft | \$2,400  | 19      | \$73 | \$1,402  | \$5,760   | \$9,562  |
| Exterior Waterproofing                         | FOUND - WP - EXT | CALC     | perimeter 176 LF [S100]                             | 176   | lf   | \$21,252 | 264     | \$73 | \$19,272 | —         | \$40,524 |

| DIVISION 04 — Masonry · \$25,144       |                   |          |                                               |     |      |         |         |      |          |           |          |
|----------------------------------------|-------------------|----------|-----------------------------------------------|-----|------|---------|---------|------|----------|-----------|----------|
| ITEM                                   | CODE              | METHOD   | DIMENSION BASIS [SHEET]                       | QTY | UNIT | MAT \$  | LAB-HRS | RATE | LABOR \$ | SUB-EQ \$ | TOTAL    |
| Brick Veneer                           | SID - BRICK - VEN | MEASURED | front 24'×35.3' – openings = 600 SF [A004]    | 600 | sqft | \$8,694 | 150     | \$73 | \$10,950 | —         | \$19,644 |
| Lintels, flashing, masonry accessories | ALLOWANCE         | CALC     | front openings: storefront + 8 windows [A004] | 1   | ls   | \$0     | 0       | \$73 | \$0      | \$5,500   | \$5,500  |

| DIVISION 05 — Metals (structural steel) · \$55,466       |                      |          |                                                     |     |      |          |         |      |          |           |          |
|----------------------------------------------------------|----------------------|----------|-----------------------------------------------------|-----|------|----------|---------|------|----------|-----------|----------|
| ITEM                                                     | CODE                 | METHOD   | DIMENSION BASIS [SHEET]                             | QTY | UNIT | MAT \$   | LAB-HRS | RATE | LABOR \$ | SUB-EQ \$ | TOTAL    |
| Steel Beam Installation                                  | FOUND - STEEL - BEAM | MEASURED | W12×26: ~2 beams × 24' × 4 levels + roof [S101]     | 210 | lf   | \$12,678 | 158     | \$73 | \$11,498 | —         | \$24,175 |
| HSS 5×5×3/8 steel columns + base plates                  | ALLOWANCE            | MEASURED | ~8 cols × 35' on 3/4"×8"×12 base plates [S100/S101] | 280 | lf   | \$6,076  | 35      | \$73 | \$2,535  | \$8,680   | \$17,291 |
| Steel connections, embeds, stair/rail steel, misc metals | ALLOWANCE            | CALC     | beam/col connections + egress stair steel [S101]    | 1   | ls   | \$0      | 0       | \$73 | \$0      | \$14,000  | \$14,000 |

| DIVISION 06 — Wood, Plastics & Rough Carpentry · \$159,625 |                      |          |                                    |       |      |          |         |      |          |           |          |
|------------------------------------------------------------|----------------------|----------|------------------------------------|-------|------|----------|---------|------|----------|-----------|----------|
| ITEM                                                       | CODE                 | METHOD   | DIMENSION BASIS [SHEET]            | QTY   | UNIT | MAT \$   | LAB-HRS | RATE | LABOR \$ | SUB-EQ \$ | TOTAL    |
| Floor System – I-Joist (TJI)                               | FRAME - FLOOR - TJI  | MEASURED | 3 floors × 1,480 = 4,440 SF [S101] | 4,440 | sqft | \$33,700 | 266     | \$73 | \$19,447 | —         | \$53,147 |
| Subfloor Sheathing                                         | FRAME - SHEATH - SUB | MEASURED | 3/4" ply, 4,440 SF [S101]          | 4,440 | sqft | \$12,654 | 133     | \$73 | \$9,724  | —         | \$22,378 |
| Exterior Wall – 2x6                                        | FRAME - WALL - 2X6   | CALC     | P176 × 3 stories = 528 LF [A004]   | 528   | lf   | \$6,009  | 95      | \$73 | \$6,938  | —         | \$12,947 |

| DIVISION 06 — Wood, Plastics & Rough Carpentry · \$159,625 |                   |          |                                                                 |       |      |          |         |      |          |           |          |
|------------------------------------------------------------|-------------------|----------|-----------------------------------------------------------------|-------|------|----------|---------|------|----------|-----------|----------|
| ITEM                                                       | CODE              | METHOD   | DIMENSION BASIS [SHEET]                                         | QTY   | UNIT | MAT \$   | LAB-HRS | RATE | LABOR \$ | SUB-EQ \$ | TOTAL    |
| Interior Wall – 2x4                                        | FRAME-WALL - 2X4  | MEASURED | partitions: cellar130+1st120+2nd210+3rd210 = 700 LF [A001-A002] | 700   | lf   | \$5,313  | 105     | \$73 | \$7,665  | —         | \$12,978 |
| Wall Sheathing – OSB/Plywood                               | FRAME-SHEATH-WALL | CALC     | P176 × 30' above grade = 5,280 SF [A004]                        | 5,280 | sqft | \$10,032 | 106     | \$73 | \$7,709  | —         | \$17,741 |
| Low-slope roof framing (PT 2x8 @24" + steel)               | ALLOWANCE         | MEASURED | roof 1,480 SF [S101/A003]                                       | 1,480 | sqft | \$5,550  | 74      | \$73 | \$5,402  | —         | \$10,952 |
| Roof Sheathing – OSB/Plywood                               | FRAME-SHEATH-ROOF | MEASURED | 1,480 SF [A003]                                                 | 1,480 | sqft | \$2,990  | 44      | \$73 | \$3,241  | —         | \$6,231  |
| Stair Framing                                              | FRAME-STAIR       | MEASURED | cellar → 3 = 4 flights, 18-19 risers ea [A001-A002]             | 4     | each | \$725    | 16      | \$73 | \$1,168  | —         | \$1,893  |
| Elevator shaft framing & 2-hr rated enclosure              | ALLOWANCE         | MEASURED | 7'-9"×7'-9" × 4 levels shaft [A001]                             | 1     | ea   | \$0      | 0       | \$73 | \$0      | \$14,000  | \$14,000 |
| Blocking, backing, misc rough carpentry                    | ALLOWANCE         | CALC     | GSF 5,920 [A001-A002]                                           | 5,920 | sqft | \$3,730  | 50      | \$73 | \$3,630  | —         | \$7,360  |

| DIVISION 07 — Thermal, Moisture & Exterior · \$113,419 |                  |          |                                                 |       |      |          |         |      |          |           |          |
|--------------------------------------------------------|------------------|----------|-------------------------------------------------|-------|------|----------|---------|------|----------|-----------|----------|
| ITEM                                                   | CODE             | METHOD   | DIMENSION BASIS [SHEET]                         | QTY   | UNIT | MAT \$   | LAB-HRS | RATE | LABOR \$ | SUB-EQ \$ | TOTAL    |
| Batt Insulation – R-13/R-15                            | FRAME-INSUL-BATT | CALC     | exterior walls 5,280 SF [A004]                  | 5,280 | sqft | \$5,122  | 53      | \$73 | \$3,854  | —         | \$8,976  |
| Fiber Cement Siding – Lap                              | SID-FC-LAP       | MEASURED | rear 728 + 2 sides 4,372 = 5,100 SF [A004/A005] | 5,100 | sqft | \$33,864 | 408     | \$73 | \$29,784 | —         | \$63,648 |
| Roof / rigid insulation + air/vapor barrier            | ALLOWANCE        | MEASURED | roof 1,480 SF [A003]                            | 1,480 | sqft | \$2,324  | 22      | \$73 | \$1,631  | \$2,664   | \$6,619  |
| House wrap / weather-resistive barrier                 | ALLOWANCE        | CALC     | 5,280 SF [A004]                                 | 5,280 | sqft | \$3,590  | 48      | \$73 | \$3,508  | —         | \$7,098  |
| TPO Flat Roof                                          | R00F-FLAT-TPO    | MEASURED | 1,480 SF = 14.8 sq [A003]                       | 14.8  | sq   | \$4,914  | 37      | \$73 | \$2,701  | —         | \$7,615  |
| Gutters, downspouts, flashing, coping                  | ALLOWANCE        | CALC     | parapet perimeter + downspouts [A003/A004]      | 1     | ls   | \$0      | 0       | \$73 | \$0      | \$8,500   | \$8,500  |
| Firestopping / rated assemblies (Type IIIB)            | ALLOWANCE        | CALC     | GSF 5,920 rated construction [A000]             | 5,920 | sqft | \$1,302  | 17      | \$73 | \$1,253  | \$3,907   | \$6,463  |
| Sealants & caulking                                    | ALLOWANCE        | CALC     | openings + joints perimeter [A004]              | 1     | ls   | \$0      | 0       | \$73 | \$0      | \$4,500   | \$4,500  |

| DIVISION 08 — Openings · \$63,921 |                |          |                                     |     |      |          |         |      |          |           |          |
|-----------------------------------|----------------|----------|-------------------------------------|-----|------|----------|---------|------|----------|-----------|----------|
| ITEM                              | CODE           | METHOD   | DIMENSION BASIS [SHEET]             | QTY | UNIT | MAT \$   | LAB-HRS | RATE | LABOR \$ | SUB-EQ \$ | TOTAL    |
| Interior Door – Solid Core        | D00R-INT-SOLID | MEASURED | D2xx/D3xx interior [A006/plans]     | 40  | each | \$14,490 | 100     | \$73 | \$7,300  | —         | \$21,790 |
| Exterior Door – Steel             | D00R-EXT-STEEL | MEASURED | front dbl + rear + side [A004/A005] | 4   | each | \$2,898  | 16      | \$73 | \$1,168  | —         | \$4,066  |

| DIVISION 08 — Openings · \$63,921               |                |          |                                                             |        |      |          |         |      |          |           |          |
|-------------------------------------------------|----------------|----------|-------------------------------------------------------------|--------|------|----------|---------|------|----------|-----------|----------|
| ITEM                                            | CODE           | METHOD   | DIMENSION BASIS [SHEET]                                     | QTY    | UNIT | MAT \$   | LAB-HRS | RATE | LABOR \$ | SUB-EQ \$ | TOTAL    |
| Vinyl Double-Hung Window                        | WIN-VIN-DH     | MEASURED | window tags 01–35 [A004/A005]                               | 35     | each | \$15,848 | 88      | \$73 | \$6,388  | —         | \$22,236 |
| Storefront / WELCOME entry glazing              | ALLOWANCE      | MEASURED | first-floor storefront + WELCOME entry (elevation) [A004]   | 1      | ls   | \$0      | 0       | \$73 | \$0      | \$9,500   | \$9,500  |
| Commercial hardware (levers, closers, panic)    | ALLOWANCE      | CALC     | 44 doors × commercial hardware set [plans]                  | 44     | ea   | \$4,466  | 26      | \$73 | \$1,863  | —         | \$6,329  |
| DIVISION 09 — Finishes · \$246,524              |                |          |                                                             |        |      |          |         |      |          |           |          |
| ITEM                                            | CODE           | METHOD   | DIMENSION BASIS [SHEET]                                     | QTY    | UNIT | MAT \$   | LAB-HRS | RATE | LABOR \$ | SUB-EQ \$ | TOTAL    |
| Drywall Hang — Standard 1/2\                    | DRY-HANG-STD   | CALC     | 2.4×GSF walls + ceilings [A001-A002]                        | 26,084 | sqft | \$18,259 | 522     | \$73 | \$38,083 | —         | \$56,341 |
| Drywall Tape & Finish — Level 4                 | DRY-TAPE-L4    | CALC     | same drywall area, Level-4 finish [A001-A002]               | 26,084 | sqft | \$7,825  | 522     | \$73 | \$38,083 | —         | \$45,908 |
| Rated shaft/corridor drywall upgrade (Type X)   | ALLOWANCE      | CALC     | elevator shaft + corridor rated walls ~3,500 SF [A001-A002] | 3,500  | sqft | \$1,540  | 31      | \$73 | \$2,248  | —         | \$3,788  |
| Suspended ACT ceilings (cellar/kitchen/support) | ALLOWANCE      | CALC     | kitchen 470 + records/maint/support ~1,600 SF [A001]        | 1,600  | sqft | \$3,456  | 31      | \$73 | \$2,243  | \$5,760   | \$11,459 |
| Porcelain Floor Tile                            | FLR-TILE-PORC  | MEASURED | 7 baths tile floor+base ~900 SF [A001-A002]                 | 900    | sqft | \$8,694  | 180     | \$73 | \$13,140 | —         | \$21,834 |
| Luxury Vinyl Plank (LVP)                        | FLR-LVP        | CALC     | 8 BR + lounge/office/common ~4,500 SF [A001-A002]           | 4,500  | sqft | \$21,735 | 270     | \$73 | \$19,710 | —         | \$41,445 |
| Interior Wall Paint                             | PAINT-INT-WALL | CALC     | wall+ceiling drywall area [A001-A002]                       | 26,084 | sqft | \$12,520 | 522     | \$73 | \$38,083 | —         | \$50,603 |
| Finish carpentry — base, casing, trim           | ALLOWANCE      | CALC     | GSF 5,920 base/casing at doors+rooms [A001-A002]            | 5,920  | sqft | \$6,157  | 123     | \$73 | \$8,989  | —         | \$15,146 |
| DIVISION 10 — Specialties · \$13,561            |                |          |                                                             |        |      |          |         |      |          |           |          |
| ITEM                                            | CODE           | METHOD   | DIMENSION BASIS [SHEET]                                     | QTY    | UNIT | MAT \$   | LAB-HRS | RATE | LABOR \$ | SUB-EQ \$ | TOTAL    |
| ADA Grab Bar                                    | BATH-ACC-GRAB  | MEASURED | 3 bars × 7 baths (ADA) [A001-A002]                          | 21     | each | \$1,521  | 21      | \$73 | \$1,533  | —         | \$3,054  |
| Toilet accessories sets (7 baths)               | ALLOWANCE      | MEASURED | 7 baths [A001-A002]                                         | 7      | ea   | \$1,078  | 6       | \$73 | \$450    | —         | \$1,528  |
| Signage — egress / ADA / room ID                | ALLOWANCE      | CALC     | ~30 rooms/egress points × ID sign [A001-A002]               | 30     | ea   | \$2,940  | 17      | \$73 | \$1,226  | —         | \$4,166  |
| Fire extinguishers & cabinets                   | ALLOWANCE      | CALC     | 4 levels, ~1 per 75' travel = 8 [A001-A002]                 | 8      | ea   | \$1,056  | 4       | \$73 | \$257    | —         | \$1,313  |
| Misc specialties (lockers, mail, corner guards) | ALLOWANCE      | CALC     | corner guards at corridors + mail [A001-A002]               | 1      | ls   | \$0      | 0       | \$73 | \$0      | \$3,500   | \$3,500  |

| DIVISION 12 — Furnishings (built-in) · \$21,734      |                |          |                                                                   |       |      |         |         |         |          |           |          |
|------------------------------------------------------|----------------|----------|-------------------------------------------------------------------|-------|------|---------|---------|---------|----------|-----------|----------|
| ITEM                                                 | CODE           | METHOD   | DIMENSION BASIS [SHEET]                                           | QTY   | UNIT | MAT \$  | LAB-HRS | RATE    | LABOR \$ | SUB-EQ \$ | TOTAL    |
| Standard Vanity with Top                             | BATH-VAN-STD   | MEASURED | 7 baths [A001-A002]                                               | 7     | each | \$4,226 | 21      | \$73    | \$1,533  | —         | \$5,759  |
| Common/kitchen casework & countertops (base-bldg)    | ALLOWANCE      | MEASURED | kitchen prep counters + server station ~40 LF [A001]              | 40    | lf   | \$3,360 | 19      | \$73    | \$1,402  | \$4,800   | \$9,562  |
| Closet/pantry shelving & built-ins                   | ALLOWANCE      | MEASURED | WIC 205/207 + closets 206 + pantry [A002]                         | 4     | ea   | \$3,250 | 43      | \$73    | \$3,163  | —         | \$6,413  |
| DIVISION 21 — Fire Suppression · \$53,980            |                |          |                                                                   |       |      |         |         |         |          |           |          |
| ITEM                                                 | CODE           | METHOD   | DIMENSION BASIS [SHEET]                                           | QTY   | UNIT | MAT \$  | LAB-HRS | RATE    | LABOR \$ | SUB-EQ \$ | TOTAL    |
| Sprinkler system — NFPA 13, full building            | ALLOWANCE      | MEASURED | GSF 5,920; sprinkler closet L3 [A002]                             | 5,920 | sqft | \$0     | 0       | \$87.25 | \$0      | \$38,480  | \$38,480 |
| Fire service / standpipe / FDC                       | ALLOWANCE      | CALC     | 1 fire service entry + riser, cellar → roof [A002]                | 1     | ls   | \$0     | 0       | \$87.25 | \$0      | \$12,000  | \$12,000 |
| Sprinkler testing & certification                    | ALLOWANCE      | CALC     | per-system flush/test [A002]                                      | 1     | ls   | \$0     | 0       | \$87.25 | \$0      | \$3,500   | \$3,500  |
| DIVISION 22 — Plumbing · \$104,100                   |                |          |                                                                   |       |      |         |         |         |          |           |          |
| ITEM                                                 | CODE           | METHOD   | DIMENSION BASIS [SHEET]                                           | QTY   | UNIT | MAT \$  | LAB-HRS | RATE    | LABOR \$ | SUB-EQ \$ | TOTAL    |
| Standard Toilet                                      | BATH-TOIL-STD  | MEASURED | 7 baths [A001-A002]                                               | 7     | each | \$2,324 | 14      | \$87.25 | \$1,222  | —         | \$3,546  |
| Lavatories / sinks (7 baths + common + kitchen)      | ALLOWANCE      | MEASURED | 7 lav + kitchen/prep/mop sinks = 12 [P102-P104]                   | 12    | ea   | \$2,232 | 48      | \$87.25 | \$4,188  | \$4,092   | \$10,512 |
| Standard Bathtub                                     | BATH-TUB-STD   | MEASURED | 30×60 tub/shower × 7 baths [A001-A002]                            | 7     | each | \$3,381 | 35      | \$87.25 | \$3,054  | —         | \$6,435  |
| DWV + water supply distribution (by fixture)         | ALLOWANCE      | MEASURED | ~36 fixtures on sanitary/water risers [P104/P105]                 | 36    | ea   | \$6,840 | 216     | \$87.25 | \$18,846 | \$17,100  | \$42,786 |
| Gas Line — New Run                                   | PLUMB-GAS-LINE | MEASURED | gas riser: kitchen + 2 WH + dryer (~180 LF) [P106]                | 180   | lf   | \$2,608 | 45      | \$87.25 | \$3,926  | —         | \$6,534  |
| Water heaters — commercial (2 × WH-1)                | ALLOWANCE      | MEASURED | 2 × WH-1 scheduled [E101/P]                                       | 2     | ea   | \$3,360 | 16      | \$87.25 | \$1,396  | \$4,200   | \$8,956  |
| Laundry rough-in + sump pump                         | ALLOWANCE      | MEASURED | washer/dryer 202 + sump pump [A002/E101]                          | 1     | ls   | \$480   | 11      | \$87.25 | \$931    | \$1,920   | \$3,331  |
| Commercial-kitchen plumbing/gas rough-in (base-bldg) | ALLOWANCE      | MEASURED | kitchen 470 SF: sinks, floor drains, gas, walk-in drains [A001/P] | 1     | ls   | \$0     | 0       | \$87.25 | \$0      | \$22,000  | \$22,000 |



| DIVISION 23 — HVAC · \$122,549                                                |               |          |                                                              |       |      |          |         |         |          |           |          |
|-------------------------------------------------------------------------------|---------------|----------|--------------------------------------------------------------|-------|------|----------|---------|---------|----------|-----------|----------|
| ITEM                                                                          | CODE          | METHOD   | DIMENSION BASIS [SHEET]                                      | QTY   | UNIT | MAT \$   | LAB-HRS | RATE    | LABOR \$ | SUB-EQ \$ | TOTAL    |
| Split HVAC systems — 4 zones (CU-1..4 + AHU-1..4)                             | ALLOWANCE     | MEASURED | 4 CU + 4 AHU scheduled [E101/M103]                           | 4     | ea   | \$15,680 | 64      | \$87.25 | \$5,584  | \$19,600  | \$40,864 |
| Ductwork distribution                                                         | ALLOWANCE     | CALC     | 4 systems × ~225 LF trunk+branch [M103/M104]                 | 900   | lf   | \$5,940  | 270     | \$87.25 | \$23,558 | \$9,900   | \$39,398 |
| Controls / thermostats / zoning                                               | ALLOWANCE     | CALC     | 4 zones × thermostat/controls [M103]                         | 4     | ea   | \$0      | 0       | \$87.25 | \$0      | \$7,500   | \$7,500  |
| Bathroom Exhaust Fan – Standard                                               | BATH-VENT-STD | MEASURED | 7 baths [M103]                                               | 7     | each | \$761    | 18      | \$87.25 | \$1,527  | —         | \$2,288  |
| Kitchen hood curb, exhaust (KEF-1) & make-up air (MAU-1) ductwork (base-bldg) | ALLOWANCE     | MEASURED | KEF-1 + MAU-1 scheduled [E101/M]                             | 1     | ls   | \$0      | 0       | \$87.25 | \$0      | \$26,000  | \$26,000 |
| Elevator machine-room mini-split + TAB                                        | ALLOWANCE     | MEASURED | elevator mini-split scheduled [E101]                         | 1     | ls   | \$0      | 0       | \$87.25 | \$0      | \$6,500   | \$6,500  |
| DIVISION 26 — Electrical · \$140,745                                          |               |          |                                                              |       |      |          |         |         |          |           |          |
| ITEM                                                                          | CODE          | METHOD   | DIMENSION BASIS [SHEET]                                      | QTY   | UNIT | MAT \$   | LAB-HRS | RATE    | LABOR \$ | SUB-EQ \$ | TOTAL    |
| Panel Upgrade – 400A                                                          | ELEC-PNL-400  | MEASURED | 400A/208V/3Φ service + CT/meter (riser) [E101]               | 1     | each | \$4,226  | 24      | \$87.25 | \$2,094  | —         | \$6,320  |
| Panel Upgrade – 200A                                                          | ELEC-PNL-200  | MEASURED | panels A + B (schedules) [E101]                              | 2     | each | \$3,381  | 28      | \$87.25 | \$2,443  | —         | \$5,824  |
| Feeders & branch wiring (building-wide)                                       | ALLOWANCE     | CALC     | ~80 circuits (panel A+B) × avg run over 5,920 SF [E101-E104] | 5,920 | sqft | \$19,654 | 296     | \$87.25 | \$25,826 | \$22,496  | \$67,976 |
| Lighting package (LED recessed/surface, interior/exterior)                    | ALLOWANCE     | MEASURED | ~65 fixtures counted on E104 + controls [E104]               | 65    | ea   | \$7,605  | 45      | \$87.25 | \$3,932  | \$5,915   | \$17,452 |
| Wiring devices & plates                                                       | ALLOWANCE     | CALC     | receptacle circuits × devices/circuit [E102-E103]            | 220   | ea   | \$3,696  | 74      | \$87.25 | \$6,450  | —         | \$10,146 |
| HVAC power / equipment connections (CU/AHU/MAU/KEF)                           | ALLOWANCE     | MEASURED | 4 CU + 4 AHU + MAU + KEF = 10 connections [E101]             | 10    | ea   | \$2,600  | 52      | \$87.25 | \$4,537  | —         | \$7,137  |
| Commercial-kitchen & walk-in electrical rough-in (base-bldg)                  | ALLOWANCE     | MEASURED | kitchen + walk-in cooler circuits (panel A) [E101]           | 1     | ls   | \$0      | 0       | \$87.25 | \$0      | \$11,000  | \$11,000 |
| Elevator power rough-in, disconnect & cab-light circuit                       | ALLOWANCE     | MEASURED | elevator machine + cab-light circuits (panel B) [E101]       | 1     | ls   | \$0      | 0       | \$87.25 | \$0      | \$5,200   | \$5,200  |
| Emergency & exit lighting (egress)                                            | ALLOWANCE     | CALC     | egress path exit/EM combos, 4 levels [E104]                  | 24    | ea   | \$4,608  | 41      | \$87.25 | \$3,574  | —         | \$8,182  |

| DIVISION 26 — Electrical · \$140,745                           |            |          |                                                          |       |      |         |         |         |          |           |          |
|----------------------------------------------------------------|------------|----------|----------------------------------------------------------|-------|------|---------|---------|---------|----------|-----------|----------|
| ITEM                                                           | CODE       | METHOD   | DIMENSION BASIS [SHEET]                                  | QTY   | UNIT | MAT \$  | LAB-HRS | RATE    | LABOR \$ | SUB-EQ \$ | TOTAL    |
| Smoke Detector – Hardwired                                     | ELEC-SMOKE | MEASURED | smoke/CO detectors, ~14 bedrooms/corridors [E101 legend] | 14    | each | \$592   | 11      | \$87.25 | \$916    | —         | \$1,508  |
| DIVISION 27/28 — Communications & Electronic Safety · \$35,862 |            |          |                                                          |       |      |         |         |         |          |           |          |
| ITEM                                                           | CODE       | METHOD   | DIMENSION BASIS [SHEET]                                  | QTY   | UNIT | MAT \$  | LAB-HRS | RATE    | LABOR \$ | SUB-EQ \$ | TOTAL    |
| Fire alarm system — addressable (R-2)                          | ALLOWANCE  | CALC     | GSF 5,920; smoke/CO devices per E101 legend [E101/A000]  | 5,920 | sqft | \$0     | 0       | \$87.25 | \$0      | \$15,392  | \$15,392 |
| Cat6 Ethernet Drop                                             | ELEC-CAT6  | CALC     | ~20 data drops (1-2 per office/common) [E102 note A]     | 20    | each | \$725   | 20      | \$87.25 | \$1,745  | —         | \$2,470  |
| Security / access control / intercom / CCTV                    | ALLOWANCE  | ASSUMED  |                                                          | 1     | ls   | \$0     | 0       | \$87.25 | \$0      | \$18,000  | \$18,000 |
| DIVISION 31 — Earthwork · \$55,343                             |            |          |                                                          |       |      |         |         |         |          |           |          |
| ITEM                                                           | CODE       | METHOD   | DIMENSION BASIS [SHEET]                                  | QTY   | UNIT | MAT \$  | LAB-HRS | RATE    | LABOR \$ | SUB-EQ \$ | TOTAL    |
| Mass & foundation excavation (cellar)                          | ALLOWANCE  | CALC     | 1,480 SF × 10' / 27 = 548 CY [S100]                      | 550   | cy   | \$0     | 62      | \$73    | \$4,497  | \$18,480  | \$22,977 |
| Haul-off / spoil disposal                                      | ALLOWANCE  | CALC     | excav 550 – backfill 180 = ~370 CY export [S100]         | 400   | cy   | \$0     | 41      | \$73    | \$2,958  | \$12,160  | \$15,118 |
| Backfill & compaction                                          | ALLOWANCE  | CALC     | perimeter over-dig backfill [S100]                       | 180   | cy   | \$0     | 24      | \$73    | \$1,787  | \$4,284   | \$6,071  |
| Stone base / under-slab drainage                               | ALLOWANCE  | MEASURED | 4" gravel under slab = 1,480 SF (S100) [S100]            | 1,480 | sqft | \$2,842 | 25      | \$73    | \$1,847  | —         | \$4,689  |
| Fine grading                                                   | ALLOWANCE  | CALC     | yard = lot 4,000 – footprint 1,480 = 2,520 SF [A000]     | 2,520 | sqft | \$0     | 35      | \$73    | \$2,557  | \$3,931   | \$6,488  |
| DIVISION 32 — Exterior Improvements · \$32,256                 |            |          |                                                          |       |      |         |         |         |          |           |          |
| ITEM                                                           | CODE       | METHOD   | DIMENSION BASIS [SHEET]                                  | QTY   | UNIT | MAT \$  | LAB-HRS | RATE    | LABOR \$ | SUB-EQ \$ | TOTAL    |
| Walks, steps & entry hardscape                                 | ALLOWANCE  | CALC     | front walk + rear egress path ~500 SF [A000]             | 500   | sqft | \$2,250 | 18      | \$73    | \$1,314  | \$5,400   | \$8,964  |
| Site drainage / area drains                                    | ALLOWANCE  | CALC     | areaway + downspout tie-ins [A000]                       | 1     | ls   | \$0     | 0       | \$73    | \$0      | \$9,500   | \$9,500  |
| Landscaping, planter & site restoration                        | ALLOWANCE  | CALC     | yard 2,520 SF + front planter [A001]                     | 2,520 | sqft | \$4,158 | 37      | \$73    | \$2,704  | \$6,930   | \$13,792 |
| DIVISION 33 — Utilities · \$62,000                             |            |          |                                                          |       |      |         |         |         |          |           |          |
| ITEM                                                           | CODE       | METHOD   | DIMENSION BASIS [SHEET]                                  | QTY   | UNIT | MAT \$  | LAB-HRS | RATE    | LABOR \$ | SUB-EQ \$ | TOTAL    |
| Domestic water service & tap                                   | ALLOWANCE  | ASSUMED  | [P102]                                                   | 1     | ls   | \$0     | 0       | \$73    | \$0      | \$18,000  | \$18,000 |
| Sanitary sewer service & connection                            | ALLOWANCE  | ASSUMED  | [P104]                                                   | 1     | ls   | \$0     | 0       | \$73    | \$0      | \$20,000  | \$20,000 |

DIVISION 33 — Utilities · \$62,000

| ITEM                                                         | CODE      | METHOD  | DIMENSION<br>BASIS [SHEET] | QTY | UNIT | MAT<br>\$ | LAB-<br>HRS | RATE | LABOR<br>\$ | SUB-EQ<br>\$ | TOTAL    |
|--------------------------------------------------------------|-----------|---------|----------------------------|-----|------|-----------|-------------|------|-------------|--------------|----------|
| Gas service & meter                                          | ALLOWANCE | ASSUMED | [P106]                     | 1   | Is   | \$0       | 0           | \$73 | \$0         | \$9,000      | \$9,000  |
| Electrical service<br>lateral / transformer<br>coord (Pepco) | ALLOWANCE | ASSUMED | [E101]                     | 1   | Is   | \$0       | 0           | \$73 | \$0         | \$15,000     | \$15,000 |

Kealee Platform · Estimate generated from packages/estimating catalogue (MARKETPLACE\_ASSEMBLIES, DC-Baltimore 2024-25, DC region factor 1.15) and cross-checked against the Construction Task Catalog (data/ctc, DMV-2026). Planning-grade estimate: quantities assumed/calculated (no measured takeoff), ±25–35% likely until a drawing-based takeoff is performed. Not a bid. Elevator and commercial-kitchen equipment excluded from all base totals and scheduled separately.