

Construction Estimate — Breakdown

5213 Call Place SE, Washington DC 20019 · New-construction detached group home / residential care (R-2), Type IIIB · Cellar + 3 stories · 5,920 GSF · 8 BR / 14 beds / 7 baths / 1 commercial kitchen / 1 elevator
Priced through the Kealee catalogue (packages/estimating, DC factor 1.15) · Markups OH 12% / Profit 15% / Contingency 7% · **6-month construction schedule** · Generated 2026-07-14

Basis of estimate — measured from the permit set (28 sheets). 88.1% of direct cost is dimensioned (measured off schedules/plans or calculated from drawing dimensions); every line below lists its dimensional basis and sheet. The remaining 12% is scope that cannot be measured from this set: Division 01 general conditions (time/effort-based), utility service laterals (no civil sheet), and security (not designed). Drawings stamped NOT FOR PERMITTING — estimation only. Persisted to Postgres (quick_estimates + estimate_line_items).

Recommended target: \$294/SF–\$300/SF (\$1,738,656–\$1.78M base building)

The \$170/SF (\$1,006,400) target is **not achievable** for a cellar+3, elevatored, sprinklered, masonry R-2 group home in DC without deleting code-required life-safety, accessibility, or structural scope.

Executive summary — scenario comparison

SCENARIO	TOTAL (EXCL. ELEVATOR + KITCHEN EQUIP)	\$/GSF	\$/BED	VS \$170/SF
A — Catalogue Market	\$2,325,179	\$393/SF	\$166,084	+131%
B — Value-Engineered	\$2,018,971	\$341/SF	\$144,212	+101%
C — Minimum Viable	\$1,738,656	\$294/SF	\$124,190	+73%
Target	\$1,006,400	\$170/SF	\$71,886	—

CTC cross-check: the same takeoff priced against the Construction Task Catalog (data/ctc) totals **\$2,234,427 (\$377/SF)** — within **-3.9%** of Scenario A. Only 45.7% of direct cost maps to a real CTC task (41-task sample); the rest is allowance.
Labor wage schedule: apprentice \$55 · journeyman \$85 · master \$124/hr. Labor = labor-hours × crew rate — general trades **\$73/hr** (60% journeyman + 40% apprentice); licensed MEP/fire **\$124/hr** (master flat (Div 21/22/23/26/27-28)). Div 01 general conditions salaried; subcontractor lump sums keep quoted value.

Scenario A — cost build-up

DIRECT CONSTRUCTION	MATERIAL	LABOR	SUBCONTRACTOR	LABOR-HOURS
\$1,694,698	\$462,742	\$625,729	\$573,506	7,553
Direct construction	\$1,694,698			
GC overhead (12%)	\$203,364			
GC profit (15%)	\$254,205			
Contingency (7%)	\$118,629			
Bonds & insurance (1.5%)	\$32,284			
Permit allowance (DCRA)	\$22,000			
TOTAL (excl. elevator + kitchen equip)	\$2,325,179			

CSI division summary

DIV	DESCRIPTION	SCENARIO A	SCENARIO B	SCENARIO C	A LAB-HRS
01	General Conditions	\$162,884	\$143,338	\$123,792	1,051
02	Existing Conditions	\$32,848	\$28,906	\$24,964	56
03	Concrete	\$143,985	\$126,706	\$109,428	501
04	Masonry	\$25,144	\$22,127	\$19,109	150
05	Metals (structural steel)	\$55,466	\$48,810	\$42,154	192
06	Wood, Plastics & Rough Carpentry	\$159,625	\$140,470	\$121,315	889
07	Thermal, Moisture & Exterior	\$113,419	\$99,809	\$86,199	585
08	Openings	\$63,921	\$56,250	\$48,580	229
09	Finishes	\$246,524	\$216,941	\$187,358	2,200
10	Specialties	\$13,561	\$11,934	\$10,307	47
12	Furnishings (built-in)	\$21,734	\$19,126	\$16,518	84
21	Fire Suppression	\$53,980	\$47,502	\$41,025	0
22	Plumbing	\$118,236	\$104,048	\$89,860	385
23	HVAC	\$135,467	\$119,211	\$102,955	352
26	Electrical	\$161,709	\$142,303	\$122,898	570
27/28	Communications & Electronic Safety	\$36,597	\$32,205	\$27,813	20
31	Earthwork	\$55,343	\$48,702	\$42,061	187
32	Exterior Improvements	\$32,256	\$28,385	\$24,515	55
33	Utilities	\$62,000	\$54,560	\$47,120	0
Direct construction		\$1,694,698	\$1,491,334	\$1,287,970	7,553

Excluded-cost schedule (NOT in any total above — owner procures separately)

Elevator — \$142,000 allowance

Passenger elevator equipment — 3,500# (A001)	\$72,000
Elevator cab, doors & landing entrances	\$22,000
Rails, controls & fixtures	\$18,000
Elevator installation labor	\$24,000
Testing, inspection & DCRA certification	\$6,000
Elevator total	\$142,000

Included in base building: elevator pit (Div 03), hoistway shaft framing + 2-hr rated enclosure (Div 06), power rough-in & disconnect (Div 26).

Commercial kitchen equipment — \$120,500 allowance

Type I exhaust hood package (KEF-1)	\$14,000
Hood fire suppression (Ansul)	\$6,500
Make-up air unit MAU-1 (if equipment-scoped)	\$12,000
Walk-in refrigerator (A001)	\$11,000
Walk-in freezer (A001)	\$13,000
Cooking equipment (double oven + line)	\$28,000
Commercial dishwasher	\$9,000
Stainless prep tables, sinks, shelving	\$12,000

Loose / owner-furnished food-service equipment	\$15,000
Kitchen equipment total	\$120,500

Included in base building: kitchen plumbing/gas rough-in (Div 22), electrical rough-in (Div 26), hood curb + exhaust/MUA ductwork (Div 23), kitchen wall/floor/ceiling finishes (Div 09).

Owner cash-flow summary (Scenario A base building)

BASE BUILDING	PER GSF	PER BED (14)	PER BEDROOM (8)	PER BATHROOM (7)
\$2,325,179	\$393/SF	\$166,084	\$290,647	\$332,168

Base-building construction (excl. elevator + kitchen equip)	\$2,325,179
Separate elevator allowance	\$142,000
Separate kitchen-equipment allowance	\$120,500
All-in incl. excluded allowances	\$2,587,679

Detailed line-item breakdown — Scenario A

shaded rows = labeled temporary allowance (no catalogue assembly). Code column shows the Kealee catalogue code or ALLOWANCE. Sub-Eq/u = subcontractor or equipment unit cost.

DIVISION 01 — General Conditions · \$162,884											
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT \$	LAB-HRS	RATE	LABOR \$	SUB-EQ \$	TOTAL
Project Management – Weekly	GEN-PM-WEEKLY	CALC	6-mo schedule = 26 wk	26	each	\$0	208	sal.	\$20,930	—	\$20,930
Site superintendent (6 mo)	ALLOWANCE	ASSUMED	6-mo build	6	mo	\$0	760	sal.	\$57,000	—	\$57,000
Mobilization / demobilization	ALLOWANCE	ASSUMED		1	ls	\$0	0	sal.	\$0	\$18,000	\$18,000
Temporary Power	GEN-TEMP-POWER	CALC	6 months	6	each	\$2,898	24	sal.	\$2,415	—	\$5,313
Temporary water / heat / enclosure	ALLOWANCE	ASSUMED		6	mo	\$0	0	sal.	\$0	\$5,100	\$5,100
Portable Toilet – Monthly	GEN-PORT-TOILET	CALC	6 months	6	each	\$1,268	0	sal.	\$0	—	\$1,268
Safety / OSHA / PPE program	ALLOWANCE	ASSUMED		1	ls	\$0	0	sal.	\$0	\$14,000	\$14,000
Dumpster – 30 Yard	GEN-DUMP-30	CALC		10	each	\$7,245	0	sal.	\$0	—	\$7,245
Final Construction Cleanup	GEN-CLEANUP-FINAL	MEASURED	GSF 5,920 [A001-A002]	5,920	sqft	\$1,776	59	sal.	\$3,078	—	\$4,854
Testing & special inspections (Type IIIB + steel)	ALLOWANCE	ASSUMED	[A000/S101]	1	ls	\$0	0	sal.	\$0	\$18,000	\$18,000
Property Survey	GEN-SURVEY	CALC		1	each	\$725	0	sal.	\$0	—	\$725
Structural Engineering	GEN-ENGINEER	CALC	[S101]	1	each	\$1,449	0	sal.	\$0	—	\$1,449
Closeout / as-builts / O&M / commissioning	ALLOWANCE	ASSUMED		1	ls	\$0	0	sal.	\$0	\$9,000	\$9,000
DIVISION 02 — Existing Conditions · \$32,848											
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT \$	LAB-HRS	RATE	LABOR \$	SUB-EQ \$	TOTAL
Clearing & site preparation	ALLOWANCE	CALC	lot 4,000 SF (20'×100' / 40'×100') [A000]	4,000	sqft	\$0	32	\$73	\$2,336	\$9,600	\$11,936
Erosion & sediment control (DOEE/SWM)	ALLOWANCE	CALC	lot perimeter silt fence ~280 LF [A000]	280	lf	\$2,688	24	\$73	\$1,744	\$4,480	\$8,912
New rear areaway excavation/retaining	ALLOWANCE	MEASURED	rear areaway shown (scope note) [A000]	1	ls	\$0	0	\$73	\$0	\$12,000	\$12,000

DIVISION 03 — Concrete · \$143,985											
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT \$	LAB-HRS	RATE	LABOR \$	SUB-EQ \$	TOTAL
Drilled piers 18"Ø×30" (4-#5 vert, #3 ties)	ALLOWANCE	MEASURED	18"Ø×30" deep × ~10 at HSS cols/perimeter [S100]	10	ea	\$4,125	0	\$73	\$0	\$12,375	\$16,500
Grade beams / foundation wall — 8" CIP	ALLOWANCE	CALC	P176 × 9' cellar = 1,584 SF [S100]	1,584	sqft	\$13,464	144	\$73	\$10,488	\$29,621	\$53,573
Concrete Pour — 4\	CONC - POUR - 4	MEASURED	4" SOG, 24×~62 = 1,480 SF [S100]	1,480	sqft	\$8,036	59	\$73	\$4,322	—	\$12,358
Wire Mesh Placement	CONC - MESH	MEASURED	W2.9×W2.9 WWF over slab area [S100]	1,480	sqft	\$888	15	\$73	\$1,080	—	\$1,968
Elevator pit (excavate/form/pour/waterproof)	ALLOWANCE	MEASURED	7'-9"×7'-9" hoistway pit [A001]	1	ea	\$0	0	\$73	\$0	\$9,500	\$9,500
Exterior concrete (rear areaway, stoop, steps)	ALLOWANCE	MEASURED	rear areaway + front entry slab ~400 SF [A000/S100]	400	sqft	\$2,400	19	\$73	\$1,402	\$5,760	\$9,562
Exterior Waterproofing	FOUND - WP - EXT	CALC	perimeter 176 LF [S100]	176	lf	\$21,252	264	\$73	\$19,272	—	\$40,524

DIVISION 04 — Masonry · \$25,144											
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT \$	LAB-HRS	RATE	LABOR \$	SUB-EQ \$	TOTAL
Brick Veneer	SID - BRICK - VEN	MEASURED	front 24'×35.3' – openings = 600 SF [A004]	600	sqft	\$8,694	150	\$73	\$10,950	—	\$19,644
Lintels, flashing, masonry accessories	ALLOWANCE	CALC	front openings: storefront + 8 windows [A004]	1	ls	\$0	0	\$73	\$0	\$5,500	\$5,500

DIVISION 05 — Metals (structural steel) · \$55,466											
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT \$	LAB-HRS	RATE	LABOR \$	SUB-EQ \$	TOTAL
Steel Beam Installation	FOUND - STEEL - BEAM	MEASURED	W12×26: ~2 beams × 24' × 4 levels + roof [S101]	210	lf	\$12,678	158	\$73	\$11,498	—	\$24,175
HSS 5×5×3/8 steel columns + base plates	ALLOWANCE	MEASURED	~8 cols × 35' on 3/4"×8"×12 base plates [S100/S101]	280	lf	\$6,076	35	\$73	\$2,535	\$8,680	\$17,291
Steel connections, embeds, stair/rail steel, misc metals	ALLOWANCE	CALC	beam/col connections + egress stair steel [S101]	1	ls	\$0	0	\$73	\$0	\$14,000	\$14,000

DIVISION 06 — Wood, Plastics & Rough Carpentry · \$159,625											
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT \$	LAB-HRS	RATE	LABOR \$	SUB-EQ \$	TOTAL
Floor System – I-Joist (TJI)	FRAME - FLOOR - TJI	MEASURED	3 floors × 1,480 = 4,440 SF [S101]	4,440	sqft	\$33,700	266	\$73	\$19,447	—	\$53,147
Subfloor Sheathing	FRAME - SHEATH - SUB	MEASURED	3/4" ply, 4,440 SF [S101]	4,440	sqft	\$12,654	133	\$73	\$9,724	—	\$22,378
Exterior Wall – 2x6	FRAME - WALL - 2X6	CALC	P176 × 3 stories = 528 LF [A004]	528	lf	\$6,009	95	\$73	\$6,938	—	\$12,947

DIVISION 06 — Wood, Plastics & Rough Carpentry · \$159,625											
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT \$	LAB-HRS	RATE	LABOR \$	SUB-EQ \$	TOTAL
Interior Wall – 2x4	FRAME-WALL - 2X4	MEASURED	partitions: cellar130+1st120+2nd210+3rd210 = 700 LF [A001-A002]	700	lf	\$5,313	105	\$73	\$7,665	—	\$12,978
Wall Sheathing – OSB/Plywood	FRAME-SHEATH-WALL	CALC	P176 × 30' above grade = 5,280 SF [A004]	5,280	sqft	\$10,032	106	\$73	\$7,709	—	\$17,741
Low-slope roof framing (PT 2x8 @24" + steel)	ALLOWANCE	MEASURED	roof 1,480 SF [S101/A003]	1,480	sqft	\$5,550	74	\$73	\$5,402	—	\$10,952
Roof Sheathing – OSB/Plywood	FRAME-SHEATH-ROOF	MEASURED	1,480 SF [A003]	1,480	sqft	\$2,990	44	\$73	\$3,241	—	\$6,231
Stair Framing	FRAME-STAIR	MEASURED	cellar → 3 = 4 flights, 18-19 risers ea [A001-A002]	4	each	\$725	16	\$73	\$1,168	—	\$1,893
Elevator shaft framing & 2-hr rated enclosure	ALLOWANCE	MEASURED	7'-9"×7'-9" × 4 levels shaft [A001]	1	ea	\$0	0	\$73	\$0	\$14,000	\$14,000
Blocking, backing, misc rough carpentry	ALLOWANCE	CALC	GSF 5,920 [A001-A002]	5,920	sqft	\$3,730	50	\$73	\$3,630	—	\$7,360

DIVISION 07 — Thermal, Moisture & Exterior · \$113,419											
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT \$	LAB-HRS	RATE	LABOR \$	SUB-EQ \$	TOTAL
Batt Insulation – R-13/R-15	FRAME-INSUL-BATT	CALC	exterior walls 5,280 SF [A004]	5,280	sqft	\$5,122	53	\$73	\$3,854	—	\$8,976
Fiber Cement Siding – Lap	SID-FC-LAP	MEASURED	rear 728 + 2 sides 4,372 = 5,100 SF [A004/A005]	5,100	sqft	\$33,864	408	\$73	\$29,784	—	\$63,648
Roof / rigid insulation + air/vapor barrier	ALLOWANCE	MEASURED	roof 1,480 SF [A003]	1,480	sqft	\$2,324	22	\$73	\$1,631	\$2,664	\$6,619
House wrap / weather-resistive barrier	ALLOWANCE	CALC	5,280 SF [A004]	5,280	sqft	\$3,590	48	\$73	\$3,508	—	\$7,098
TPO Flat Roof	R00F-FLAT-TPO	MEASURED	1,480 SF = 14.8 sq [A003]	14.8	sq	\$4,914	37	\$73	\$2,701	—	\$7,615
Gutters, downspouts, flashing, coping	ALLOWANCE	CALC	parapet perimeter + downspouts [A003/A004]	1	ls	\$0	0	\$73	\$0	\$8,500	\$8,500
Firestopping / rated assemblies (Type IIIB)	ALLOWANCE	CALC	GSF 5,920 rated construction [A000]	5,920	sqft	\$1,302	17	\$73	\$1,253	\$3,907	\$6,463
Sealants & caulking	ALLOWANCE	CALC	openings + joints perimeter [A004]	1	ls	\$0	0	\$73	\$0	\$4,500	\$4,500

DIVISION 08 — Openings · \$63,921											
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT \$	LAB-HRS	RATE	LABOR \$	SUB-EQ \$	TOTAL
Interior Door – Solid Core	D00R-INT-SOLID	MEASURED	D2xx/D3xx interior [A006/plans]	40	each	\$14,490	100	\$73	\$7,300	—	\$21,790
Exterior Door – Steel	D00R-EXT-STEEL	MEASURED	front dbl + rear + side [A004/A005]	4	each	\$2,898	16	\$73	\$1,168	—	\$4,066

DIVISION 08 — Openings · \$63,921											
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT \$	LAB-HRS	RATE	LABOR \$	SUB-EQ \$	TOTAL
Vinyl Double-Hung Window	WIN-VIN-DH	MEASURED	window tags 01–35 [A004/A005]	35	each	\$15,848	88	\$73	\$6,388	—	\$22,236
Storefront / WELCOME entry glazing	ALLOWANCE	MEASURED	first-floor storefront + WELCOME entry (elevation) [A004]	1	ls	\$0	0	\$73	\$0	\$9,500	\$9,500
Commercial hardware (levers, closers, panic)	ALLOWANCE	CALC	44 doors × commercial hardware set [plans]	44	ea	\$4,466	26	\$73	\$1,863	—	\$6,329
DIVISION 09 — Finishes · \$246,524											
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT \$	LAB-HRS	RATE	LABOR \$	SUB-EQ \$	TOTAL
Drywall Hang — Standard 1/2\	DRY-HANG-STD	CALC	2.4×GSF walls + ceilings [A001-A002]	26,084	sqft	\$18,259	522	\$73	\$38,083	—	\$56,341
Drywall Tape & Finish — Level 4	DRY-TAPE-L4	CALC	same drywall area, Level-4 finish [A001-A002]	26,084	sqft	\$7,825	522	\$73	\$38,083	—	\$45,908
Rated shaft/corridor drywall upgrade (Type X)	ALLOWANCE	CALC	elevator shaft + corridor rated walls ~3,500 SF [A001-A002]	3,500	sqft	\$1,540	31	\$73	\$2,248	—	\$3,788
Suspended ACT ceilings (cellar/kitchen/support)	ALLOWANCE	CALC	kitchen 470 + records/maint/support ~1,600 SF [A001]	1,600	sqft	\$3,456	31	\$73	\$2,243	\$5,760	\$11,459
Porcelain Floor Tile	FLR-TILE-PORC	MEASURED	7 baths tile floor+base ~900 SF [A001-A002]	900	sqft	\$8,694	180	\$73	\$13,140	—	\$21,834
Luxury Vinyl Plank (LVP)	FLR-LVP	CALC	8 BR + lounge/office/common ~4,500 SF [A001-A002]	4,500	sqft	\$21,735	270	\$73	\$19,710	—	\$41,445
Interior Wall Paint	PAINT-INT-WALL	CALC	wall+ceiling drywall area [A001-A002]	26,084	sqft	\$12,520	522	\$73	\$38,083	—	\$50,603
Finish carpentry — base, casing, trim	ALLOWANCE	CALC	GSF 5,920 base/casing at doors+rooms [A001-A002]	5,920	sqft	\$6,157	123	\$73	\$8,989	—	\$15,146
DIVISION 10 — Specialties · \$13,561											
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT \$	LAB-HRS	RATE	LABOR \$	SUB-EQ \$	TOTAL
ADA Grab Bar	BATH-ACC-GRAB	MEASURED	3 bars × 7 baths (ADA) [A001-A002]	21	each	\$1,521	21	\$73	\$1,533	—	\$3,054
Toilet accessories sets (7 baths)	ALLOWANCE	MEASURED	7 baths [A001-A002]	7	ea	\$1,078	6	\$73	\$450	—	\$1,528
Signage — egress / ADA / room ID	ALLOWANCE	CALC	~30 rooms/egress points × ID sign [A001-A002]	30	ea	\$2,940	17	\$73	\$1,226	—	\$4,166
Fire extinguishers & cabinets	ALLOWANCE	CALC	4 levels, ~1 per 75' travel = 8 [A001-A002]	8	ea	\$1,056	4	\$73	\$257	—	\$1,313
Misc specialties (lockers, mail, corner guards)	ALLOWANCE	CALC	corner guards at corridors + mail [A001-A002]	1	ls	\$0	0	\$73	\$0	\$3,500	\$3,500

DIVISION 12 — Furnishings (built-in) · \$21,734											
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT \$	LAB-HRS	RATE	LABOR \$	SUB-EQ \$	TOTAL
Standard Vanity with Top	BATH-VAN-STD	MEASURED	7 baths [A001-A002]	7	each	\$4,226	21	\$73	\$1,533	—	\$5,759
Common/kitchen casework & countertops (base-bldg)	ALLOWANCE	MEASURED	kitchen prep counters + server station ~40 LF [A001]	40	lf	\$3,360	19	\$73	\$1,402	\$4,800	\$9,562
Closet/pantry shelving & built-ins	ALLOWANCE	MEASURED	WIC 205/207 + closets 206 + pantry [A002]	4	ea	\$3,250	43	\$73	\$3,163	—	\$6,413

DIVISION 21 — Fire Suppression · \$53,980											
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT \$	LAB-HRS	RATE	LABOR \$	SUB-EQ \$	TOTAL
Sprinkler system — NFPA 13, full building	ALLOWANCE	MEASURED	GSF 5,920; sprinkler closet L3 [A002]	5,920	sqft	\$0	0	\$124	\$0	\$38,480	\$38,480
Fire service / standpipe / FDC	ALLOWANCE	CALC	1 fire service entry + riser, cellar → roof [A002]	1	ls	\$0	0	\$124	\$0	\$12,000	\$12,000
Sprinkler testing & certification	ALLOWANCE	CALC	per-system flush/test [A002]	1	ls	\$0	0	\$124	\$0	\$3,500	\$3,500

DIVISION 22 — Plumbing · \$118,236											
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT \$	LAB-HRS	RATE	LABOR \$	SUB-EQ \$	TOTAL
Standard Toilet	BATH-TOIL-STD	MEASURED	7 baths [A001-A002]	7	each	\$2,324	14	\$124	\$1,736	—	\$4,060
Lavatories / sinks (7 baths + common + kitchen)	ALLOWANCE	MEASURED	7 lav + kitchen/prep/mop sinks = 12 [P102-P104]	12	ea	\$2,232	48	\$124	\$5,952	\$4,092	\$12,276
Standard Bathtub	BATH-TUB-STD	MEASURED	30×60 tub/shower × 7 baths [A001-A002]	7	each	\$3,381	35	\$124	\$4,340	—	\$7,721
DWV + water supply distribution (by fixture)	ALLOWANCE	MEASURED	~36 fixtures on sanitary/water risers [P104/P105]	36	ea	\$6,840	216	\$124	\$26,784	\$17,100	\$50,724
Gas Line — New Run	PLUMB-GAS-LINE	MEASURED	gas riser: kitchen + 2 WH + dryer (~180 LF) [P106]	180	lf	\$2,608	45	\$124	\$5,580	—	\$8,188
Water heaters — commercial (2 × WH-1)	ALLOWANCE	MEASURED	2 × WH-1 scheduled [E101/P]	2	ea	\$3,360	16	\$124	\$1,984	\$4,200	\$9,544
Laundry rough-in + sump pump	ALLOWANCE	MEASURED	washer/dryer 202 + sump pump [A002/E101]	1	ls	\$480	11	\$124	\$1,323	\$1,920	\$3,723
Commercial-kitchen plumbing/gas rough-in (base-bldg)	ALLOWANCE	MEASURED	kitchen 470 SF: sinks, floor drains, gas, walk-in drains [A001/P]	1	ls	\$0	0	\$124	\$0	\$22,000	\$22,000

DIVISION 23 — HVAC · \$135,467											
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT \$	LAB- HRS	RATE	LABOR \$	SUB-EQ \$	TOTAL
Split HVAC systems — 4 zones (CU-1..4 + AHU-1..4)	ALLOWANCE	MEASURED	4 CU + 4 AHU scheduled [E101/M103]	4	ea	\$15,680	64	\$124	\$7,936	\$19,600	\$43,216
Ductwork distribution	ALLOWANCE	CALC	4 systems × ~225 LF trunk+branch [M103/M104]	900	lf	\$5,940	270	\$124	\$33,480	\$9,900	\$49,320
Controls / thermostats / zoning	ALLOWANCE	CALC	4 zones × thermostat/controls [M103]	4	ea	\$0	0	\$124	\$0	\$7,500	\$7,500
Bathroom Exhaust Fan – Standard	BATH-VENT-STD	MEASURED	7 baths [M103]	7	each	\$761	18	\$124	\$2,170	—	\$2,931
Kitchen hood curb, exhaust (KEF-1) & make-up air (MAU-1) ductwork (base-bldg)	ALLOWANCE	MEASURED	KEF-1 + MAU-1 scheduled [E101/M]	1	ls	\$0	0	\$124	\$0	\$26,000	\$26,000
Elevator machine-room mini-split + TAB	ALLOWANCE	MEASURED	elevator mini-split scheduled [E101]	1	ls	\$0	0	\$124	\$0	\$6,500	\$6,500
DIVISION 26 — Electrical · \$161,709											
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT \$	LAB- HRS	RATE	LABOR \$	SUB-EQ \$	TOTAL
Panel Upgrade – 400A	ELEC-PNL-400	MEASURED	400A/208V/3Φ service + CT/meter (riser) [E101]	1	each	\$4,226	24	\$124	\$2,976	—	\$7,202
Panel Upgrade – 200A	ELEC-PNL-200	MEASURED	panels A + B (schedules) [E101]	2	each	\$3,381	28	\$124	\$3,472	—	\$6,853
Feeders & branch wiring (building-wide)	ALLOWANCE	CALC	~80 circuits (panel A+B) × avg run over 5,920 SF [E101-E104]	5,920	sqft	\$19,654	296	\$124	\$36,704	\$22,496	\$78,854
Lighting package (LED recessed/surface, interior/exterior)	ALLOWANCE	MEASURED	~65 fixtures counted on E104 + controls [E104]	65	ea	\$7,605	45	\$124	\$5,588	\$5,915	\$19,108
Wiring devices & plates	ALLOWANCE	CALC	receptacle circuits × devices/circuit [E102-E103]	220	ea	\$3,696	74	\$124	\$9,166	—	\$12,862
HVAC power / equipment connections (CU/AHU/MAU/KEF)	ALLOWANCE	MEASURED	4 CU + 4 AHU + MAU + KEF = 10 connections [E101]	10	ea	\$2,600	52	\$124	\$6,448	—	\$9,048
Commercial-kitchen & walk-in electrical rough-in (base-bldg)	ALLOWANCE	MEASURED	kitchen + walk-in cooler circuits (panel A) [E101]	1	ls	\$0	0	\$124	\$0	\$11,000	\$11,000
Elevator power rough-in, disconnect & cab-light circuit	ALLOWANCE	MEASURED	elevator machine + cab-light circuits (panel B) [E101]	1	ls	\$0	0	\$124	\$0	\$5,200	\$5,200
Emergency & exit lighting (egress)	ALLOWANCE	CALC	egress path exit/EM combos, 4 levels [E104]	24	ea	\$4,608	41	\$124	\$5,079	—	\$9,687

DIVISION 26 — Electrical · \$161,709											
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT \$	LAB-HRS	RATE	LABOR \$	SUB-EQ \$	TOTAL
Smoke Detector – Hardwired	ELEC-SMOKE	MEASURED	smoke/CO detectors, ~14 bedrooms/corridors [E101 legend]	14	each	\$592	11	\$124	\$1,302	—	\$1,894
DIVISION 27/28 — Communications & Electronic Safety · \$36,597											
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT \$	LAB-HRS	RATE	LABOR \$	SUB-EQ \$	TOTAL
Fire alarm system — addressable (R-2)	ALLOWANCE	CALC	GSF 5,920; smoke/CO devices per E101 legend [E101/A000]	5,920	sqft	\$0	0	\$124	\$0	\$15,392	\$15,392
Cat6 Ethernet Drop	ELEC-CAT6	CALC	~20 data drops (1-2 per office/common) [E102 note A]	20	each	\$725	20	\$124	\$2,480	—	\$3,205
Security / access control / intercom / CCTV	ALLOWANCE	ASSUMED		1	ls	\$0	0	\$124	\$0	\$18,000	\$18,000
DIVISION 31 — Earthwork · \$55,343											
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT \$	LAB-HRS	RATE	LABOR \$	SUB-EQ \$	TOTAL
Mass & foundation excavation (cellar)	ALLOWANCE	CALC	1,480 SF × 10' / 27 = 548 CY [S100]	550	cy	\$0	62	\$73	\$4,497	\$18,480	\$22,977
Haul-off / spoil disposal	ALLOWANCE	CALC	excav 550 – backfill 180 = ~370 CY export [S100]	400	cy	\$0	41	\$73	\$2,958	\$12,160	\$15,118
Backfill & compaction	ALLOWANCE	CALC	perimeter over-dig backfill [S100]	180	cy	\$0	24	\$73	\$1,787	\$4,284	\$6,071
Stone base / under-slab drainage	ALLOWANCE	MEASURED	4" gravel under slab = 1,480 SF (S100) [S100]	1,480	sqft	\$2,842	25	\$73	\$1,847	—	\$4,689
Fine grading	ALLOWANCE	CALC	yard = lot 4,000 – footprint 1,480 = 2,520 SF [A000]	2,520	sqft	\$0	35	\$73	\$2,557	\$3,931	\$6,488
DIVISION 32 — Exterior Improvements · \$32,256											
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT \$	LAB-HRS	RATE	LABOR \$	SUB-EQ \$	TOTAL
Walks, steps & entry hardscape	ALLOWANCE	CALC	front walk + rear egress path ~500 SF [A000]	500	sqft	\$2,250	18	\$73	\$1,314	\$5,400	\$8,964
Site drainage / area drains	ALLOWANCE	CALC	areaway + downspout tie-ins [A000]	1	ls	\$0	0	\$73	\$0	\$9,500	\$9,500
Landscaping, planter & site restoration	ALLOWANCE	CALC	yard 2,520 SF + front planter [A001]	2,520	sqft	\$4,158	37	\$73	\$2,704	\$6,930	\$13,792
DIVISION 33 — Utilities · \$62,000											
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT \$	LAB-HRS	RATE	LABOR \$	SUB-EQ \$	TOTAL
Domestic water service & tap	ALLOWANCE	ASSUMED	[P102]	1	ls	\$0	0	\$73	\$0	\$18,000	\$18,000
Sanitary sewer service & connection	ALLOWANCE	ASSUMED	[P104]	1	ls	\$0	0	\$73	\$0	\$20,000	\$20,000

DIVISION 33 — Utilities · \$62,000

ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT \$	LAB- HRS	RATE	LABOR \$	SUB-EQ \$	TOTAL
Gas service & meter	ALLOWANCE	ASSUMED	[P106]	1	ls	\$0	0	\$73	\$0	\$9,000	\$9,000
Electrical service lateral / transformer coord (Pepco)	ALLOWANCE	ASSUMED	[E101]	1	ls	\$0	0	\$73	\$0	\$15,000	\$15,000

Kealee Platform · Estimate generated from packages/estimating catalogue (MARKETPLACE_ASSEMBLIES, DC-Baltimore 2024-25, DC region factor 1.15) and cross-checked against the Construction Task Catalog (data/ctc, DMV-2026). Planning-grade estimate: quantities assumed/calculated (no measured takeoff), ±25–35% likely until a drawing-based takeoff is performed. Not a bid. Elevator and commercial-kitchen equipment excluded from all base totals and scheduled separately.