

↑  
N

## KEALEE

design, build, deliver

PROJECT  
1005 Rollins Ave

ADDRESS  
1005 Rollins Ave

JURISDICTION  
prince georges md

ZONE  
RSF-65

SHEET  
C-200 — Overall Site and Zoning Plan

SCALE  
1" = 10'

STATUS  
PRELIMINARY

SHEET NO.  
1 OF 1

COORDINATES  
EPSG:2248

H: NAD83

V: NAVD83 (feet)

PROFESSIONAL RESPONSIBILITY

Maryland Licensed Surveyor

certifies: boundary\_determination, topographic\_survey

SEAL AND SIGNATURE

Maryland Professional Engineer

certifies: site\_layout

SEAL AND SIGNATURE

Architect

certifies: architectural\_footprint

SEAL AND SIGNATURE

This sheet carries content from more than one professional discipline. Each seal below applies only to the subjects listed beside it. No professional certifies content outside their stated scope, and the sheet is not divided into separate drawings for that purpose.

| SITE DATA          |               |          |  |
|--------------------|---------------|----------|--|
| ZONE               | RSF-65        |          |  |
| TAX / PARCEL ID    | 348854        |          |  |
| GROSS LOT AREA     | 9,596 SF      | 0.220 AC |  |
| SETBACKS           | REQUIRED      | PROVIDED |  |
| FRONT YARD         | 25'           | 25'      |  |
| SIDE YARD          | 8'            | 8'       |  |
| REAR YARD          | 20'           | 20'      |  |
| COVERAGE           | MAX           | PROPOSED |  |
| LOT COVERAGE       | 35%           | 17.7%    |  |
| BUILDING FOOTPRINT | —             | 1,700 SF |  |
| DATUM              |               |          |  |
| HORIZONTAL         | EPSG-2248     | NAD83    |  |
| VERTICAL           | NAVD83 (feet) |          |  |

| SITE ANALYSIS           |                 |  |  |
|-------------------------|-----------------|--|--|
| 1. Gross tract area     | 9,596 SF        |  |  |
| 2. Area of dwelling     | 1,700 SF        |  |  |
| 3. Wooded area          | NOT ESTABLISHED |  |  |
| 4. Floodplain area      | NOT ESTABLISHED |  |  |
| 5. Net tract area       | 9,596 SF        |  |  |
| 6. TOTAL AREA DISTURBED | NOT QUANTIFIED  |  |  |

| SEQUENCE OF CONSTRUCTION                                                                  |  |           |  |
|-------------------------------------------------------------------------------------------|--|-----------|--|
| 1. Pre-construction meeting                                                               |  | 1 DAY     |  |
| 2. Obtain necessary permits                                                               |  | 2 DAYS    |  |
| 3. Notify Miss Utility at 811 at least 48 hours prior to any excavation                   |  | 1 DAY     |  |
| 4. Construct stabilized construction entrance and perimeter sediment control              |  | 2 DAYS    |  |
| 5. Rough grade, construct dwelling, utilities and driveway                                |  | 12 MONTHS |  |
| 6. Fine grade and stabilize all disturbed areas                                           |  | 1 DAY     |  |
| 7. Remove sediment control devices when written permission has been granted by the agency |  | 1 DAY     |  |
| TOTAL ESTIMATED TIME OF CONSTRUCTION: 12 MONTHS                                           |  |           |  |

| GENERAL NOTES                                                                                  |  |  |  |
|------------------------------------------------------------------------------------------------|--|--|--|
| 1. CONTRACTOR SHALL CONTACT MISS UTILITY AT 811 A MINIMUM OF 48 HOURS PRIOR TO ANY EXCAVATION. |  |  |  |
| 2. ALL EXISTING AND PROPOSED UTILITIES SHOWN PER PGC CODE SEC. 32.106.                         |  |  |  |
| 3. PROPOSED GRADE SHOWN SOLID EXISTING GRADE SHOWN DASHED                                      |  |  |  |
| 4. ROUGH EARTHWORK GRADES AND UTILITY ELEVATIONS SHOWN TO TENTHS OF A FOOT.                    |  |  |  |
| 5. BOUNDARY SHOWN IS COMPILED JURISDICTION GIS, NOT A BOUNDARY SURVEY.                         |  |  |  |

| LEGEND    |                                                |  |  |
|-----------|------------------------------------------------|--|--|
| —         | PROPERTY BOUNDARY                              |  |  |
| - - - - - | BRL — BUILDING RESTRICTION LINE                |  |  |
| —         | PROPOSED STRUCTURE                             |  |  |
| —         | EXISTING CONTOUR — PGATLAS 2 FT (2023), NAVD83 |  |  |
| - - - - - | STREET CENTRELINE                              |  |  |
| - - - - - | EASEMENT                                       |  |  |

| PRINCE GEORGE'S COUNTY SOIL CONSERVATION DISTRICT APPROVAL |  |      |  |
|------------------------------------------------------------|--|------|--|
| SEMI-ANNUAL, CONSERVATION, SOILS & EROSION                 |  |      |  |
| SIGNATURE                                                  |  | DATE |  |

| DPE SITE/ROAD PLAN REVIEW DIVISION APPROVAL |  |      |  |
|---------------------------------------------|--|------|--|
| SIGNATURE                                   |  | DATE |  |

| GRADING CERTIFICATE                                                                                                                                                                                                                                                                                                                                                                                                                                                                               |  |  |  |
|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|--|
| I HEREBY CERTIFY THAT THIS PLAN CONFORMS TO THE REQUIREMENTS OF SUBTITLE 32, DIVISION 2 OF THE CODE OF PRINCE GEORGE'S COUNTY WATER RESOURCES PROTECTION AND GRADING CODE AND THAT I OR MY STAFF HAVE INSPECTED THIS SITE AND THAT DRAINAGE FLOWS FROM UPHILL PROPERTIES ONTO THIS SITE, AND FROM THIS SITE ONTO DOWNHILL PROPERTIES, HAVE BEEN ADDRESSED IN SUBSTANTIAL ACCORDANCE WITH APPLICABLE CODES, SIGNED, SEALED AND DATED BY A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF MARYLAND. |  |  |  |
| Prince George's County CPE, Site Rough Grading Design Review Checklist, Item A-10                                                                                                                                                                                                                                                                                                                                                                                                                 |  |  |  |

| STABILIZATION COMPLIANCE PREAMBLE                                                                                                                                                                                                                      |  |  |  |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|--|
| Stabilization practices on all projects must be in compliance with the requirements of COMAR 26.17.02 by January 9, 2023, regardless of when an erosion and sediment control plan was approved. COMAR 26.17.02.06(C), Grandfathering of approved plans |  |  |  |

| STANDARD STABILIZATION NOTE                                                                                                                                                                                                                                                                                                                                                                                                              |  |  |  |
|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|--|
| Following initial soil disturbance or re-disturbance, permanent or temporary stabilization must be completed within (1) Three (3) calendar days as to the surface of all perimeter ditches, swales, ditches, perimeter ditches, and all slopes steeper than 1:1 horizontal to 1:1 vertical (3:1 ratio) (unless otherwise noted) (7) calendar days as to all other disturbed or graded areas on the project site not under active grading |  |  |  |
| 2021 Maryland Standards and Specifications for Soil Erosion and Sediment Control, "Standard Stabilization Note" (repealed by COMAR 26.17.02.06(C))                                                                                                                                                                                                                                                                                       |  |  |  |

REVISIONS

— NONE —

## SOILS TABLE

USDA NRCS SSURGO — required by POC Code Sec. 32-130(a)(13)

| MAP UNIT | MAP UNIT NAME                                    | K-FACTOR | HYDRIC | HYD. GROUP | DRAINAGE CLASS          |
|----------|--------------------------------------------------|----------|--------|------------|-------------------------|
| AaB      | Adelphi silt loam, 2 to 5 percent slopes complex | 37       | No     | C          | Moderately well drained |
| ACA      | Adelphi Aquasol complex, 0 to 2 percent slopes   | 43       | No     | D          | Somewhat poorly drained |
| ACA      | Adelphi Aquasol complex, 0 to 2 percent slopes   | 37       | No     | C          | Moderately well drained |
| ADA      | Adelphi Hartsel complex, 0 to 2 percent slopes   | 24       | No     | BD         | Somewhat poorly drained |
| ADA      | Adelphi Hartsel complex, 0 to 2 percent slopes   | 37       | No     | C          | Moderately well drained |
| AaB      | Adelphi Hartsel complex, 2 to 5 percent slopes   | 24       | No     | BD         | Somewhat poorly drained |
| AaB      | Adelphi Hartsel complex, 2 to 5 percent slopes   | 37       | No     | C          | Moderately well drained |
| AaC      | Adelphi Hartsel complex, 5 to 10 percent slopes  | 24       | No     | BD         | Somewhat poorly drained |

SOURCE AND ACCURACY  
Parcel boundary — Jurisdiction gis — Prince George's County / M-NCPPC — PGAtlas Property — level 1  
Existing contours — Prince George's County / M-NCPPC — PGAtlas — level 1  
Contours: PGAtlas Elevation/MapServer1 — Contour = 2 FT (2023), 2 ft interval, NAVD83 (feet)

