

Construction Estimate — Breakdown

5213 Call Place SE, Washington DC 20019 · New-construction detached group home / residential care (R-2), Type IIIB · Cellar + 3 stories · 5,920 GSF · 8 BR / 14 beds / 7 baths / 1 commercial kitchen / 1 elevator
Priced through the Kealee catalogue (packages/estimating, DC factor 1.15) · Markups OH 12% / Profit 15% / Contingency 7% ·
Generated 2026-07-14

Basis of estimate — measured from the permit set (28 sheets). 84.6% of direct cost is dimensioned (measured off schedules/plans or calculated from drawing dimensions); every line below lists its dimensional basis and sheet. The remaining 15% is scope that cannot be measured from this set: Division 01 general conditions (time/effort-based), utility service laterals (no civil sheet), and security (not designed). Drawings stamped NOT FOR PERMITTING — estimation only. Persisted to Postgres (quick_estimates + estimate_line_items).

Recommended target: \$297/SF–\$300/SF (\$1,758,292–\$1.78M base building)

The \$170/SF (\$1,006,400) target is **not achievable** for a cellar+3, elevatored, sprinklered, masonry R-2 group home in DC without deleting code-required life-safety, accessibility, or structural scope.

Executive summary — scenario comparison

SCENARIO	TOTAL (EXCL. ELEVATOR + KITCHEN EQUIP)	\$/GSF	\$/BED	VS \$170/SF
A — Catalogue Market	\$2,351,400	\$397/SF	\$167,957	+134%
B — Value-Engineered	\$2,041,706	\$345/SF	\$145,836	+103%
C — Minimum Viable	\$1,758,292	\$297/SF	\$125,592	+75%
Target	\$1,006,400	\$170/SF	\$71,886	—

CTC cross-check: the same takeoff priced against the Construction Task Catalog (data/ctc) totals **\$2,234,427 (\$377/SF)** — within **-5.0%** of Scenario A. Only **45.7%** of direct cost maps to a real CTC task (41-task sample); the rest is allowance.

Scenario A — cost build-up

DIRECT CONSTRUCTION	MATERIAL	LABOR	SUBCONTRACTOR	LABOR-HOURS
\$1,713,992	\$466,908	\$635,757	\$578,606	5,797
Direct construction	\$1,713,992			
GC overhead (12%)	\$205,679			
GC profit (15%)	\$257,099			
Contingency (7%)	\$119,979			
Bonds & insurance (1.5%)	\$32,652			
Permit allowance (DCRA)	\$22,000			
TOTAL (excl. elevator + kitchen equip)	\$2,351,400			

CSI division summary

DIV	DESCRIPTION	SCENARIO A	SCENARIO B	SCENARIO C	A LAB-HRS
01	General Conditions	\$252,495	\$222,195	\$191,896	523
02	Existing Conditions	\$32,960	\$29,005	\$25,050	0
03	Concrete	\$153,522	\$135,099	\$116,677	338
04	Masonry	\$23,854	\$20,992	\$18,129	150
05	Metals (structural steel)	\$57,320	\$50,442	\$43,563	158
06	Wood, Plastics & Rough Carpentry	\$168,718	\$148,472	\$128,225	766
07	Thermal, Moisture & Exterior	\$121,702	\$107,098	\$92,494	498
08	Openings	\$69,989	\$61,590	\$53,192	204
09	Finishes	\$230,268	\$202,636	\$175,004	2,015
10	Specialties	\$14,134	\$12,438	\$10,742	21
12	Furnishings (built-in)	\$22,339	\$19,658	\$16,977	21
21	Fire Suppression	\$53,980	\$47,502	\$41,025	0
22	Plumbing	\$93,329	\$82,129	\$70,930	374
23	HVAC	\$101,371	\$89,206	\$77,042	352
26	Electrical	\$131,527	\$115,744	\$99,961	359
27/28	Communications & Electronic Safety	\$36,417	\$32,047	\$27,677	20
31	Earthwork	\$55,708	\$49,023	\$42,338	0
32	Exterior Improvements	\$32,360	\$28,477	\$24,594	0
33	Utilities	\$62,000	\$54,560	\$47,120	0
Direct construction		\$1,713,992	\$1,508,313	\$1,302,634	5,797

Excluded-cost schedule (NOT in any total above — owner procures separately)

Elevator — \$142,000 allowance

Passenger elevator equipment — 3,500# (A001)	\$72,000
Elevator cab, doors & landing entrances	\$22,000
Rails, controls & fixtures	\$18,000
Elevator installation labor	\$24,000
Testing, inspection & DCRA certification	\$6,000
Elevator total	\$142,000

Included in base building: elevator pit (Div 03), hoistway shaft framing + 2-hr rated enclosure (Div 06), power rough-in & disconnect (Div 26).

Commercial kitchen equipment — \$120,500 allowance

Type I exhaust hood package (KEF-1)	\$14,000
Hood fire suppression (Ansul)	\$6,500
Make-up air unit MAU-1 (if equipment-scoped)	\$12,000
Walk-in refrigerator (A001)	\$11,000
Walk-in freezer (A001)	\$13,000
Cooking equipment (double oven + line)	\$28,000
Commercial dishwasher	\$9,000

Stainless prep tables, sinks, shelving	\$12,000
Loose / owner-furnished food-service equipment	\$15,000
Kitchen equipment total	\$120,500

Included in base building: kitchen plumbing/gas rough-in (Div 22), electrical rough-in (Div 26), hood curb + exhaust/MUA ductwork (Div 23), kitchen wall/floor/ceiling finishes (Div 09).

Owner cash-flow summary (Scenario A base building)

BASE BUILDING	PER GSF	PER BED (14)	PER BEDROOM (8)	PER BATHROOM (7)
\$2,351,400	\$397/SF	\$167,957	\$293,925	\$335,914

Base-building construction (excl. elevator + kitchen equip)	\$2,351,400
Separate elevator allowance	\$142,000
Separate kitchen-equipment allowance	\$120,500
All-in incl. excluded allowances	\$2,613,900

Detailed line-item breakdown — Scenario A

shaded rows = labeled temporary allowance (no catalogue assembly). Code column shows the Kealee catalogue code or ALLOWANCE. Sub-Eq/u = subcontractor or equipment unit cost.

DIVISION 01 — General Conditions · \$252,495									
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT/U	LAB/U	SUB·EQ/U	EXTENDED
Project Management – Weekly	GEN-PM-WEEKLY	CALC	12-mo schedule	52	each	\$0.00	\$805.00	—	\$41,860
Site superintendent (12 mo)	ALLOWANCE	ASSUMED	12-mo build	12	mo	\$0.00	\$9,500.00	—	\$114,000
Mobilization / demobilization	ALLOWANCE	ASSUMED		1	ls	\$0.00	\$0.00	\$18,000.00	\$18,000
Temporary Power	GEN-TEMP-POWER	CALC	monthly	12	each	\$483.00	\$402.50	—	\$10,626
Temporary water / heat / enclosure	ALLOWANCE	ASSUMED		12	mo	\$0.00	\$0.00	\$850.00	\$10,200
Portable Toilet – Monthly	GEN-PORT-TOILET	CALC		12	each	\$211.31	\$0.00	—	\$2,536
Safety / OSHA / PPE program	ALLOWANCE	ASSUMED		1	ls	\$0.00	\$0.00	\$14,000.00	\$14,000
Dumpster – 30 Yard	GEN-DUMP-30	CALC		10	each	\$724.50	\$0.00	—	\$7,245
Final Construction Cleanup	GEN-CLEANUP-FINAL	MEASURED	GSF 5,920 [A001-A002]	5,920	sqft	\$0.30	\$0.52	—	\$4,854
Testing & special inspections (Type IIIB + steel)	ALLOWANCE	ASSUMED	[A000/S101]	1	ls	\$0.00	\$0.00	\$18,000.00	\$18,000
Property Survey	GEN-SURVEY	CALC		1	each	\$724.50	\$0.00	—	\$725
Structural Engineering	GEN-ENGINEER	CALC	[S101]	1	each	\$1,449.00	\$0.00	—	\$1,449
Closeout / as-builts / O&M / commissioning	ALLOWANCE	ASSUMED		1	ls	\$0.00	\$0.00	\$9,000.00	\$9,000
DIVISION 02 — Existing Conditions · \$32,960									
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT/U	LAB/U	SUB·EQ/U	EXTENDED
Clearing & site preparation	ALLOWANCE	CALC	lot 4,000 SF (20'×100' / 40'×100') [A000]	4,000	sqft	\$0.00	\$0.60	\$1.20	\$12,000
Erosion & sediment control (DOEE/SWM)	ALLOWANCE	CALC	lot perimeter silt fence ~280 LF [A000]	280	lf	\$9.60	\$6.40	\$16.00	\$8,960
New rear areaway excavation/retaining	ALLOWANCE	MEASURED	rear areaway shown (scope note) [A000]	1	ls	\$0.00	\$0.00	\$12,000.00	\$12,000

DIVISION 03 — Concrete · \$153,522									
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT/U	LAB/U	SUB·EQ/U	EXTENDED
Drilled piers 18"Ø×30" (4-#5 vert, #3 ties)	ALLOWANCE	MEASURED	18"Ø×30" deep × ~10 at HSS cols/perimeter [S100]	10	ea	\$412.50	\$0.00	\$907.50	\$16,500
Grade beams / foundation wall — 8" CIP	ALLOWANCE	CALC	P176 × 9' cellar = 1,584 SF [S100]	1,584	sqft	\$8.50	\$6.80	\$18.70	\$53,856
Concrete Pour – 4\	CONC-POUR-4	MEASURED	4" SOG, 24x~62 = 1,480 SF [S100]	1,480	sqft	\$5.43	\$4.60	—	\$14,844
Wire Mesh Placement	CONC-MESH	MEASURED	W2.9×W2.9 WWF over slab area [S100]	1,480	sqft	\$0.60	\$0.52	—	\$1,658
Elevator pit (excavate/form/pour/waterproof)	ALLOWANCE	MEASURED	7'-9"×7'-9" hoistway pit [A001]	1	ea	\$0.00	\$0.00	\$9,500.00	\$9,500
Exterior concrete (rear areaway, stoop, steps)	ALLOWANCE	MEASURED	rear areaway + front entry slab ~400 SF [A000/S100]	400	sqft	\$6.00	\$3.60	\$14.40	\$9,600
Exterior Waterproofing	FOUND-WP-EXT	CALC	perimeter 176 LF [S100]	176	lf	\$120.75	\$149.50	—	\$47,564
DIVISION 04 — Masonry · \$23,854									
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT/U	LAB/U	SUB·EQ/U	EXTENDED
Brick Veneer	SID-BRICK-VEN	MEASURED	front 24'×35.3' – openings = 600 SF [A004]	600	sqft	\$14.49	\$16.10	—	\$18,354
Lintels, flashing, masonry accessories	ALLOWANCE	CALC	front openings: storefront + 8 windows [A004]	1	ls	\$0.00	\$0.00	\$5,500.00	\$5,500
DIVISION 05 — Metals (structural steel) · \$57,320									
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT/U	LAB/U	SUB·EQ/U	EXTENDED
Steel Beam Installation	FOUND-STEEL-BEAM	MEASURED	W12×26: ~2 beams × 24' × 4 levels + roof [S101]	210	lf	\$60.37	\$63.25	—	\$25,960
HSS 5×5×3/8 steel columns + base plates	ALLOWANCE	MEASURED	~8 cols × 35' on 3/4"×8"×12 base plates [S100/S101]	280	lf	\$21.70	\$9.30	\$31.00	\$17,360
Steel connections, embeds, stair/rail steel, misc metals	ALLOWANCE	CALC	beam/col connections + egress stair steel [S101]	1	ls	\$0.00	\$0.00	\$14,000.00	\$14,000
DIVISION 06 — Wood, Plastics & Rough Carpentry · \$168,718									
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT/U	LAB/U	SUB·EQ/U	EXTENDED
Floor System – I-Joist (TJI)	FRAME-FLOOR-TJI	MEASURED	3 floors × 1,480 = 4,440 SF [S101]	4,440	sqft	\$7.59	\$5.17	—	\$56,654
Subfloor Sheathing	FRAME-SHEATH-SUB	MEASURED	3/4" ply, 4,440 SF [S101]	4,440	sqft	\$2.85	\$2.30	—	\$22,866
Exterior Wall – 2x6	FRAME-WALL-2X6	CALC	P176 × 3 stories = 528 LF [A004]	528	lf	\$11.38	\$14.95	—	\$13,902

DIVISION 06 — Wood, Plastics & Rough Carpentry · \$168,718									
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT/U	LAB/U	SUB·EQ/U	EXTENDED
Interior Wall – 2x4	FRAME - WALL - 2X4	MEASURED	partitions: cellar130+1st120+2nd210+3rd210 = 700 LF [A001-A002]	700	lf	\$7.59	\$11.50	—	\$13,363
Wall Sheathing – OSB/Plywood	FRAME - SHEATH - WALL	CALC	P176 × 30' above grade = 5,280 SF [A004]	5,280	sqft	\$1.90	\$2.01	—	\$20,645
Low-slope roof framing (PT 2x8 @24" + steel)	ALLOWANCE	MEASURED	roof 1,480 SF [S101/A003]	1,480	sqft	\$3.75	\$3.75	—	\$11,100
Roof Sheathing – OSB/Plywood	FRAME - SHEATH - ROOF	MEASURED	1,480 SF [A003]	1,480	sqft	\$2.02	\$2.30	—	\$6,394
Stair Framing	FRAME - STAIR	MEASURED	cellar → 3 = 4 flights, 18-19 risers ea [A001-A002]	4	each	\$181.13	\$402.50	—	\$2,335
Elevator shaft framing & 2-hr rated enclosure	ALLOWANCE	MEASURED	7'-9"×7'-9" × 4 levels shaft [A001]	1	ea	\$0.00	\$0.00	\$14,000.00	\$14,000
Blocking, backing, misc rough carpentry	ALLOWANCE	CALC	GSF 5,920 [A001-A002]	5,920	sqft	\$0.63	\$0.63	—	\$7,459
DIVISION 07 — Thermal, Moisture & Exterior · \$121,702									
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT/U	LAB/U	SUB·EQ/U	EXTENDED
Batt Insulation – R-13/R-15	FRAME - INSUL - BATT	CALC	exterior walls 5,280 SF [A004]	5,280	sqft	\$0.97	\$0.98	—	\$10,296
Fiber Cement Siding – Lap	SID - FC - LAP	MEASURED	rear 728 + 2 sides 4,372 = 5,100 SF [A004/A005]	5,100	sqft	\$6.64	\$6.90	—	\$69,054
Roof / rigid insulation + air/vapor barrier	ALLOWANCE	MEASURED	roof 1,480 SF [A003]	1,480	sqft	\$1.57	\$1.13	\$1.80	\$6,660
House wrap / weather-resistive barrier	ALLOWANCE	CALC	5,280 SF [A004]	5,280	sqft	\$0.68	\$0.68	—	\$7,181
TPO Flat Roof	ROOF - FLAT - TPO	MEASURED	1,480 SF = 14.8 sq [A003]	14.8	sq	\$332.06	\$276.00	—	\$8,999
Gutters, downspouts, flashing, coping	ALLOWANCE	CALC	parapet perimeter + downspouts [A003/A004]	1	ls	\$0.00	\$0.00	\$8,500.00	\$8,500
Firestopping / rated assemblies (Type IIIB)	ALLOWANCE	CALC	GSF 5,920 rated construction [A000]	5,920	sqft	\$0.22	\$0.22	\$0.66	\$6,512
Sealants & caulking	ALLOWANCE	CALC	openings + joints perimeter [A004]	1	ls	\$0.00	\$0.00	\$4,500.00	\$4,500
DIVISION 08 — Openings · \$69,989									
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT/U	LAB/U	SUB·EQ/U	EXTENDED
Interior Door – Solid Core	D00R - INT - SOLID	MEASURED	D2xx/D3xx interior [A006/plans]	40	each	\$362.25	\$230.00	—	\$23,690

DIVISION 08 — Openings · \$69,989									
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT/U	LAB/U	SUB·EQ/U	EXTENDED
Exterior Door – Steel	D00R-EXT-STEEL	MEASURED	front dbl + rear + side [A004/A005]	4	each	\$724.50	\$402.50	—	\$4,508
Vinyl Double-Hung Window	WIN-VIN-DH	MEASURED	window tags 01–35 [A004/A005]	35	each	\$452.81	\$287.50	—	\$25,911
Storefront / WELCOME entry glazing	ALLOWANCE	MEASURED	first-floor storefront + WELCOME entry (elevation) [A004]	1	ls	\$0.00	\$0.00	\$9,500.00	\$9,500
Commercial hardware (levers, closers, panic)	ALLOWANCE	CALC	44 doors × commercial hardware set [plans]	44	ea	\$101.50	\$43.50	—	\$6,380
DIVISION 09 — Finishes · \$230,268									
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT/U	LAB/U	SUB·EQ/U	EXTENDED
Drywall Hang – Standard 1/2\	DRY-HANG-STD	CALC	2.4×GSF walls + ceilings [A001-A002]	26,084	sqft	\$0.70	\$1.15	—	\$48,255
Drywall Tape & Finish – Level 4	DRY-TAPE-L4	CALC	same drywall area, Level-4 finish [A001-A002]	26,084	sqft	\$0.30	\$1.26	—	\$40,691
Rated shaft/corridor drywall upgrade (Type X)	ALLOWANCE	CALC	elevator shaft + corridor rated walls ~3,500 SF [A001-A002]	3,500	sqft	\$0.44	\$0.66	—	\$3,850
Suspended ACT ceilings (cellar/kitchen/support)	ALLOWANCE	CALC	kitchen 470 + records/maint/support ~1,600 SF [A001]	1,600	sqft	\$2.16	\$1.44	\$3.60	\$11,520
Porcelain Floor Tile	FLR-TILE-PORC	MEASURED	7 baths tile floor+base ~900 SF [A001-A002]	900	sqft	\$9.66	\$11.50	—	\$19,044
Luxury Vinyl Plank (LVP)	FLR-LVP	CALC	8 BR + lounge/office/common ~4,500 SF [A001-A002]	4,500	sqft	\$4.83	\$3.74	—	\$38,565
Interior Wall Paint	PAINT-INT-WALL	CALC	wall+ceiling drywall area [A001-A002]	26,084	sqft	\$0.48	\$1.55	—	\$52,951
Finish carpentry — base, casing, trim	ALLOWANCE	CALC	GSF 5,920 base/casing at doors+rooms [A001-A002]	5,920	sqft	\$1.04	\$1.56	—	\$15,392
DIVISION 10 — Specialties · \$14,134									
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT/U	LAB/U	SUB·EQ/U	EXTENDED
ADA Grab Bar	BATH-ACC-GRAB	MEASURED	3 bars × 7 baths (ADA) [A001-A002]	21	each	\$72.45	\$97.75	—	\$3,574
Toilet accessories sets (7 baths)	ALLOWANCE	MEASURED	7 baths [A001-A002]	7	ea	\$154.00	\$66.00	—	\$1,540
Signage — egress / ADA / room ID	ALLOWANCE	CALC	~30 rooms/egress points × ID sign [A001-A002]	30	ea	\$98.00	\$42.00	—	\$4,200
Fire extinguishers & cabinets	ALLOWANCE	CALC	4 levels, ~1 per 75' travel = 8 [A001-A002]	8	ea	\$132.00	\$33.00	—	\$1,320
Misc specialties (lockers, mail, corner guards)	ALLOWANCE	CALC	corner guards at corridors + mail [A001-A002]	1	ls	\$0.00	\$0.00	\$3,500.00	\$3,500

DIVISION 12 — Furnishings (built-in) · \$22,339									
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT/U	LAB/U	SUB·EQ/U	EXTENDED
Standard Vanity with Top	BATH-VAN-STD	MEASURED	7 baths [A001-A002]	7	each	\$603.75	\$287.50	—	\$6,239
Common/kitchen casework & countertops (base-bldg)	ALLOWANCE	MEASURED	kitchen prep counters + server station ~40 LF [A001]	40	lf	\$84.00	\$36.00	\$120.00	\$9,600
Closet/pantry shelving & built-ins	ALLOWANCE	MEASURED	WIC 205/207 + closets 206 + pantry [A002]	4	ea	\$812.50	\$812.50	—	\$6,500
DIVISION 21 — Fire Suppression · \$53,980									
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT/U	LAB/U	SUB·EQ/U	EXTENDED
Sprinkler system — NFPA 13, full building	ALLOWANCE	MEASURED	GSF 5,920; sprinkler closet L3 [A002]	5,920	sqft	\$0.00	\$0.00	\$6.50	\$38,480
Fire service / standpipe / FDC	ALLOWANCE	CALC	1 fire service entry + riser, cellar → roof [A002]	1	ls	\$0.00	\$0.00	\$12,000.00	\$12,000
Sprinkler testing & certification	ALLOWANCE	CALC	per-system flush/test [A002]	1	ls	\$0.00	\$0.00	\$3,500.00	\$3,500
DIVISION 22 — Plumbing · \$93,329									
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT/U	LAB/U	SUB·EQ/U	EXTENDED
Standard Toilet	BATH-TOIL-STD	MEASURED	7 baths [A001-A002]	7	each	\$332.06	\$230.00	—	\$3,934
Lavatories / sinks (7 baths + common + kitchen)	ALLOWANCE	MEASURED	7 lav + kitchen/prep/mop sinks = 12 [P102-P104]	12	ea	\$186.00	\$93.00	\$341.00	\$7,440
Standard Bathtub	BATH-TUB-STD	MEASURED	30×60 tub/shower × 7 baths [A001-A002]	7	each	\$483.00	\$575.00	—	\$7,406
DWV + water supply distribution (by fixture)	ALLOWANCE	MEASURED	~36 fixtures on sanitary/water risers [P104/P105]	36	ea	\$190.00	\$285.00	\$475.00	\$34,200
Gas Line — New Run	PLUMB-GAS-LINE	MEASURED	gas riser: kitchen + 2 WH + dryer (~180 LF) [P106]	180	lf	\$14.49	\$23.00	—	\$6,748
Water heaters — commercial (2 × WH-1)	ALLOWANCE	MEASURED	2 × WH-1 scheduled [E101/P]	2	ea	\$1,680.00	\$420.00	\$2,100.00	\$8,400
Laundry rough-in + sump pump	ALLOWANCE	MEASURED	washer/dryer 202 + sump pump [A002/E101]	1	ls	\$480.00	\$800.00	\$1,920.00	\$3,200
Commercial-kitchen plumbing/gas rough-in (base-bldg)	ALLOWANCE	MEASURED	kitchen 470 SF: sinks, floor drains, gas, walk-in drains [A001/P]	1	ls	\$0.00	\$0.00	\$22,000.00	\$22,000
DIVISION 23 — HVAC · \$101,371									
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT/U	LAB/U	SUB·EQ/U	EXTENDED
Split HVAC systems — 4 zones (CU-1..4 + AHU-1..4)	ALLOWANCE	MEASURED	4 CU + 4 AHU scheduled [E101/M103]	4	ea	\$3,920.00	\$980.00	\$4,900.00	\$39,200
Ductwork distribution	ALLOWANCE	CALC	4 systems × ~225 LF trunk+branch [M103/M104]	900	lf	\$6.60	\$4.40	\$11.00	\$19,800

DIVISION 23 — HVAC · \$101,371									
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT/U	LAB/U	SUB-EQ/U	EXTENDED
Controls / thermostats / zoning	ALLOWANCE	CALC	4 zones × thermostat/controls [M103]	4	ea	\$0.00	\$0.00	\$1,875.00	\$7,500
Bathroom Exhaust Fan — Standard	BATH-VENT-STD	MEASURED	7 baths [M103]	7	each	\$108.67	\$230.00	—	\$2,371
Kitchen hood curb, exhaust (KEF-1) & make-up air (MAU-1) ductwork (base-bldg)	ALLOWANCE	MEASURED	KEF-1 + MAU-1 scheduled [E101/M]	1	ls	\$0.00	\$0.00	\$26,000.00	\$26,000
Elevator machine-room mini-split + TAB	ALLOWANCE	MEASURED	elevator mini-split scheduled [E101]	1	ls	\$0.00	\$0.00	\$6,500.00	\$6,500
DIVISION 26 — Electrical · \$131,527									
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT/U	LAB/U	SUB-EQ/U	EXTENDED
Panel Upgrade — 400A	ELEC-PNL-400	MEASURED	400A/208V/3Φ service + CT/meter (riser) [E101]	1	each	\$4,226.25	\$4,600.00	—	\$8,826
Panel Upgrade — 200A	ELEC-PNL-200	MEASURED	panels A + B (schedules) [E101]	2	each	\$1,690.50	\$2,300.00	—	\$7,981
Feeders & branch wiring (building-wide)	ALLOWANCE	CALC	~80 circuits (panel A+B) × avg run over 5,920 SF [E101-E104]	5,920	sqft	\$3.32	\$2.38	\$3.80	\$56,240
Lighting package (LED recessed/surface, interior/exterior)	ALLOWANCE	MEASURED	~65 fixtures counted on E104 + controls [E104]	65	ea	\$117.00	\$52.00	\$91.00	\$16,900
Wiring devices & plates	ALLOWANCE	CALC	receptacle circuits × devices/circuit [E102-E103]	220	ea	\$16.80	\$25.20	—	\$9,240
HVAC power / equipment connections (CU/AHU/MAU/KEF)	ALLOWANCE	MEASURED	4 CU + 4 AHU + MAU + KEF = 10 connections [E101]	10	ea	\$260.00	\$390.00	—	\$6,500
Commercial-kitchen & walk-in electrical rough-in (base-bldg)	ALLOWANCE	MEASURED	kitchen + walk-in cooler circuits (panel A) [E101]	1	ls	\$0.00	\$0.00	\$11,000.00	\$11,000
Elevator power rough-in, disconnect & cab-light circuit	ALLOWANCE	MEASURED	elevator machine + cab-light circuits (panel B) [E101]	1	ls	\$0.00	\$0.00	\$5,200.00	\$5,200
Emergency & exit lighting (egress)	ALLOWANCE	CALC	egress path exit/EM combos, 4 levels [E104]	24	ea	\$192.00	\$128.00	—	\$7,680
Smoke Detector — Hardwired	ELEC-SMOKE	MEASURED	smoke/CO detectors, ~14 bedrooms/corridors [E101 legend]	14	each	\$42.26	\$97.75	—	\$1,960
DIVISION 27/28 — Communications & Electronic Safety · \$36,417									
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT/U	LAB/U	SUB-EQ/U	EXTENDED
Fire alarm system — addressable (R-2)	ALLOWANCE	CALC	GSF 5,920; smoke/CO devices per E101 legend [E101/A000]	5,920	sqft	\$0.00	\$0.00	\$2.60	\$15,392

DIVISION 27/28 — Communications & Electronic Safety · \$36,417									
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT/U	LAB/U	SUB-EQ/U	EXTENDED
Cat6 Ethernet Drop	ELEC-CAT6	CALC	~20 data drops (1-2 per office/common) [E102 note A]	20	each	\$36.23	\$115.00	—	\$3,025
Security / access control / intercom / CCTV	ALLOWANCE	ASSUMED		1	ls	\$0.00	\$0.00	\$18,000.00	\$18,000
DIVISION 31 — Earthwork · \$55,708									
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT/U	LAB/U	SUB-EQ/U	EXTENDED
Mass & foundation excavation (cellar)	ALLOWANCE	CALC	1,480 SF × 10' / 27 = 548 CY [S100]	550	cy	\$0.00	\$8.40	\$12.60	\$23,100
Haul-off / spoil disposal	ALLOWANCE	CALC	excav 550 – backfill 180 = ~370 CY export [S100]	400	cy	\$0.00	\$7.60	\$15.20	\$15,200
Backfill & compaction	ALLOWANCE	CALC	perimeter over-dig backfill [S100]	180	cy	\$0.00	\$10.20	\$6.80	\$6,120
Stone base / under-slab drainage	ALLOWANCE	MEASURED	4" gravel under slab = 1,480 SF (S100) [S100]	1,480	sqft	\$1.92	\$1.28	—	\$4,736
Fine grading	ALLOWANCE	CALC	yard = lot 4,000 – footprint 1,480 = 2,520 SF [A000]	2,520	sqft	\$0.00	\$1.04	\$1.56	\$6,552
DIVISION 32 — Exterior Improvements · \$32,360									
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT/U	LAB/U	SUB-EQ/U	EXTENDED
Walks, steps & entry hardscape	ALLOWANCE	CALC	front walk + rear egress path ~500 SF [A000]	500	sqft	\$4.50	\$2.70	\$10.80	\$9,000
Site drainage / area drains	ALLOWANCE	CALC	areaway + downspout tie-ins [A000]	1	ls	\$0.00	\$0.00	\$9,500.00	\$9,500
Landscaping, planter & site restoration	ALLOWANCE	CALC	yard 2,520 SF + front planter [A001]	2,520	sqft	\$1.65	\$1.10	\$2.75	\$13,860
DIVISION 33 — Utilities · \$62,000									
ITEM	CODE	METHOD	DIMENSION BASIS [SHEET]	QTY	UNIT	MAT/U	LAB/U	SUB-EQ/U	EXTENDED
Domestic water service & tap	ALLOWANCE	ASSUMED	[P102]	1	ls	\$0.00	\$0.00	\$18,000.00	\$18,000
Sanitary sewer service & connection	ALLOWANCE	ASSUMED	[P104]	1	ls	\$0.00	\$0.00	\$20,000.00	\$20,000
Gas service & meter	ALLOWANCE	ASSUMED	[P106]	1	ls	\$0.00	\$0.00	\$9,000.00	\$9,000
Electrical service lateral / transformer coord (Pepco)	ALLOWANCE	ASSUMED	[E101]	1	ls	\$0.00	\$0.00	\$15,000.00	\$15,000

Kealee Platform · Estimate generated from packages/estimating catalogue (MARKETPLACE_ASSEMBLIES, DC-Baltimore 2024-25, DC region factor 1.15) and cross-checked against the Construction Task Catalog (data/ctc, DMV-2026). Planning-grade estimate: quantities assumed/calculated (no measured takeoff), ±25–35% likely until a drawing-based takeoff is performed. Not a bid. Elevator and commercial-kitchen equipment excluded from all base totals and scheduled separately.