



KEALEE

Design, build, deliver

PROJECT
Porter Subdivision — LOT 1 & LOT 2

ADDRESS
1005 Rollins Ave

JURISDICTION
prince georges md

ZONE
RSF-65

SHEET
C-001 — Site Development Plan — Existing, Proposed, Grading, Paving and Landscape

SCALE
1" = 20'

STATUS
PRELIMINARY

SHEET NO.
1 OF 1

COORDINATES
EPSG:2248
H: NAD83
V: NAVD88 (feet)

PLAN TYPE AND PREPARATION

PLAN TYPE SITE DEVELOPMENT / FINE GRADING

SHEET C-001 — Site Development Plan — Existing, Proposed, Grading, Paving and Landscape

DISCIPLINE Maryland Professional Engineer / Surveyor (see divided responsibility)

DRAWN BY KEALEE SITE-PLAN ENGINE (AUTOMATED)

DESIGNED BY — (TO BE COMPLETED BY THE DESIGN PROFESSIONAL)

CHECKED BY — (TO BE COMPLETED BY THE DESIGN PROFESSIONAL)

REVISIONS

NO.	DATE	DESCRIPTION

SITE DATA

ZONE	RSF-65
TAX / PARCEL ID	—
GROSS LOT AREA	21,826 SF 0.501 AC
LOT FRONTAGE	45' MIN 65.00'
SETBACKS	REQUIRED PROVIDED
FRONT YARD	20' 20'
SIDE YARD	8' 8'
REAR YARD	20' 20'
COVERAGE	MAX PROPOSED
LOT COVERAGE	35% 5.9%
BUILDING FOOTPRINT	— 1,196 SF
DATUM	
HORIZONTAL	EPSG:2248 NAD83
VERTICAL	NAVD88 (feet)

SITE ANALYSIS

- Gross tract area 21,826 SF
- Area of dwelling 1,196 SF
- Wooded area NOT ESTABLISHED
- Floodplain area NOT ESTABLISHED
- Net tract area 21,826 SF
- TOTAL AREA DISTURBED NOT QUANTIFIED

BUILDING DATA

	G	B	FF	SF	HT	STY
DWELLING 1	—	—	—	—	—	—
DWELLING 2	—	—	—	—	—	—

G garage slab · B basement · FF finished floor · SF subfloor · HT height · STY storerooms · A DASH IS NOT ZERO: the elevation has not been established and must be set from a field-run topographic survey before construction.

DRAINAGE AREA COMPUTATIONS

CATCHMENT	SF	ACRES	C
Total — 15.8% impervious	9,599	0.220	—
PRE-DEVELOPMENT	SF	—	C
Pervious — lawn / meadow	9,599	—	0.25
Composite C	—	—	0.250
POST-DEVELOPMENT	SF	—	C
Proposed roof	1,196	—	0.95
Driveway and on-lot paving	322	—	0.95
Pervious — lawn	8,081	—	0.25
Composite C	—	—	0.361

Flow path 204 R

Flow path slope —

Time of concentration (Kirpich) —

Rainfall intensity, 10-yr —

Peak discharge PHE, Q = CIA —

Peak discharge POST, Q = CIA —

INCREASE TO BE MANAGED —

Rv = 0.05 + 0.009 I 0.1923

Water quality volume WQv 154 cf

Water quality volume on a 1.0 in rainfall. Maryland Stormwater Design Manual, Vol. I & II — WQv on a 1.0 in rainfall.

Rundoff coefficients: roof and pavement 0.95, average lawn 0.25. Confirm the lawn coefficient against the soil hydrology group before relying on the composite.

Sidewalk, curb and gutter and the driveway apron lie in the public right-of-way and drain to the street. They are excluded from the lot catchment and included in the disturbed area.

SEQUENCE OF CONSTRUCTION

- Pre-construction meeting
- Obtain necessary permits
- Notify Miss Utility at 811 at least 48 hours prior to any excavation
- Install stabilized construction entrance and perimeter sediment control
- Rough grade the lot
- Construct dwelling
- Install water, sewer and storm services and the driveway
- Fine grade and stabilize all disturbed areas
- Remove sediment control once the inspector gives written permission

TOTAL ESTIMATED TIME OF CONSTRUCTION: 8 MONTHS

GENERAL NOTES

- CONTRACTOR SHALL CONTACT MISS UTILITY AT 811 A MINIMUM OF 48 HOURS PRIOR TO ANY EXCAVATION. FIELD-VERIFY LOCATION AND DEPTH BY TEST PIT BEFORE CONSTRUCTION.
- ALL EXISTING AND PROPOSED UTILITIES SHOWN PER PGC CODE SEC. 32-106.
- PROPOSED GRADE SHOWN SOLID; EXISTING GRADE SHOWN DASHED.
- ROUGH EARTHWORK GRADES AND UTILITY ELEVATIONS SHOWN TO TENTHS OF A FOOT.
- BOUNDARY SHOWN IS THE RECORDED PLAT OF SUBDIVISION — PORTER SUBDIVISION, LOTS 1 AND 2 — PLAT BOOK PM 231, P. 50 (MSA, C281, 19850). SEAT PLEASANT (8TH ELECTION DISTRICT, PRINCE GEORGE'S COUNTY, MARYLAND TAX MAP 73, GRID B3, 200 MAP 202 SE 36, ZONE R-45 AT RECORDING (RSF-65 UNDER THE 2022 REWRITE). SCALE 1" = 20', NOVEMBER 2007. M-NCPPC RECORD FILE 5-09121. BASIS OF BEARINGS: MARYLAND STATE PLANE COORDINATE SYSTEM (NAD 83). LOT 1 = 15,696 SQ FT (0.2283 AC); LOT 2 = 6,008 SQ FT (0.1338 AC); 4,219 SQ FT (0.0969 AC) DEDICATED TO PUBLIC USE. — TRANSCRIBED AND CHECKED FOR CLOSURE. THE PLAT IS THE BOUNDARY SURVEY. NO FIELD TOPOGRAPHY IS INCLUDED; EXISTING GRADE IS COUNTY LIDAR CONTOUR MAPPING.
- CONNECT TO EXISTING INWENT, CURB AND GUTTER, DRIVEWAY AND SIDEWALK IN LINE AND GRADE.

LEGEND

- PROPERTY BOUNDARY
- BRL — BUILDING RESTRICTION LINE
- PROPOSED STRUCTURE
- EXISTING CONTOUR — 2 FT INTERVAL, NAVD88
- STREET CENTRELINE
- PROPOSED PAVEMENT — DRIVEWAY / WALK
- EASEMENT

PROFESSIONAL CERTIFICATION


I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND.

SIGNATURE	DATE
LICENSE NO.	EXPIRATION DATE
SEAL	

REVISIONS


— NONE —

CONCRETE CURB AND GUTTER — PGC DPW&T STD. 300.01



REPRODUCED FROM THE PRINCE GEORGE'S COUNTY DPW&T STANDARD. THE STANDARD GOVERNS.

CONCRETE SIDEWALK RAMP TYPE A — PGC DPW&T STD. 300.07



REPRODUCED FROM THE PRINCE GEORGE'S COUNTY DPW&T STANDARD. THE STANDARD GOVERNS.

GRAPHIC SCALE — 1" = 20'

