

Construction Estimate — Breakdown

5213 Call Place SE, Washington DC 20019 · New-construction detached group home / residential care (R-2), Type IIIB · Cellar + 3 stories · 5,920 GSF · 8 BR / 14 beds / 7 baths / 1 commercial kitchen / 1 elevator
Priced through the Kealee catalogue (packages/estimating, DC factor 1.15) · Markups OH 12% / Profit 15% / Contingency 7% ·
Generated 2026-07-14

Basis of estimate. No permit drawings were available — **no measured takeoff** was performed. All quantities are calculated from the stated building basis or assumed as gross-area allowances (confidence LOW–MED). 66 of 106 line items are labeled temporary allowances for institutional scope the catalogue does not carry. Not persisted to a database (no DATABASE_URL in the run environment).

Recommended target: \$293/SF–\$300/SF (\$1,733,320–\$1.78M base building)

The \$170/SF (\$1,006,400) target is **not achievable** for a cellar+3, elevatored, sprinklered, masonry R-2 group home in DC without deleting code-required life-safety, accessibility, or structural scope.

Executive summary — scenario comparison

SCENARIO	TOTAL (EXCL. ELEVATOR + KITCHEN EQUIP)	\$/GSF	\$/BED	VS \$170/SF
A — Catalogue Market	\$2,318,053	\$392/SF	\$165,575	+130%
B — Value-Engineered	\$2,012,792	\$340/SF	\$143,771	+100%
C — Minimum Viable	\$1,733,320	\$293/SF	\$123,809	+72%
Target	\$1,006,400	\$170/SF	\$71,886	—

CTC cross-check: the same takeoff priced against the Construction Task Catalog (data/ctc) totals **\$2,234,427 (\$377/SF)** — within -3.6% of Scenario A. Only 45.7% of direct cost maps to a real CTC task (41-task sample); the rest is allowance.

Scenario A — cost build-up

DIRECT CONSTRUCTION

\$1,689,454

MATERIAL

\$450,055

LABOR

\$609,158

SUBCONTRACTOR

\$609,552

LABOR-HOURS

5,554

Direct construction	\$1,689,454
GC overhead (12%)	\$202,735
GC profit (15%)	\$253,418
Contingency (7%)	\$118,262
Bonds & insurance (1.5%)	\$32,184
Permit allowance (DCRA)	\$22,000
TOTAL (excl. elevator + kitchen equip)	\$2,318,053

CSI division summary

DIV	DESCRIPTION	SCENARIO A	SCENARIO B	SCENARIO C	A LAB-HRS
01	General Conditions	\$252,495	\$222,195	\$191,896	523

DIV	DESCRIPTION	SCENARIO A	SCENARIO B	SCENARIO C	A LAB-HRS
02	Existing Conditions	\$33,000	\$29,040	\$25,080	0
03	Concrete	\$149,628	\$131,673	\$113,717	414
04	Masonry	\$25,995	\$22,876	\$19,756	168
05	Metals (structural steel)	\$57,320	\$50,442	\$43,563	158
06	Wood, Plastics & Rough Carpentry	\$176,354	\$155,191	\$134,029	826
07	Thermal, Moisture & Exterior	\$116,286	\$102,332	\$88,377	466
08	Openings	\$69,989	\$61,590	\$53,192	204
09	Finishes	\$197,171	\$173,510	\$149,850	1,650
10	Specialties	\$14,134	\$12,438	\$10,742	21
12	Furnishings (built-in)	\$22,339	\$19,658	\$16,977	21
21	Fire Suppression	\$53,980	\$47,502	\$41,025	0
22	Plumbing	\$93,329	\$82,129	\$70,930	374
23	HVAC	\$101,371	\$89,206	\$77,042	352
26	Electrical	\$139,491	\$122,752	\$106,013	359
27/28	Communications & Electronic Safety	\$36,417	\$32,047	\$27,677	20
31	Earthwork	\$55,656	\$48,977	\$42,299	0
32	Exterior Improvements	\$32,500	\$28,600	\$24,700	0
33	Utilities	\$62,000	\$54,560	\$47,120	0
Direct construction		\$1,689,454	\$1,486,720	\$1,283,985	5,554

Excluded-cost schedule (NOT in any total above — owner procures separately)

Elevator — \$142,000 allowance

Passenger elevator equipment — 3,500# (A001)	\$72,000
Elevator cab, doors & landing entrances	\$22,000
Rails, controls & fixtures	\$18,000
Elevator installation labor	\$24,000
Testing, inspection & DCRA certification	\$6,000
Elevator total	\$142,000

Included in base building: elevator pit (Div 03), hoistway shaft framing + 2-hr rated enclosure (Div 06), power rough-in & disconnect (Div 26).

Commercial kitchen equipment — \$120,500 allowance

Type I exhaust hood package (KEF-1)	\$14,000
Hood fire suppression (Ansul)	\$6,500
Make-up air unit MAU-1 (if equipment-scoped)	\$12,000
Walk-in refrigerator (A001)	\$11,000
Walk-in freezer (A001)	\$13,000
Cooking equipment (double oven + line)	\$28,000
Commercial dishwasher	\$9,000
Stainless prep tables, sinks, shelving	\$12,000
Loose / owner-furnished food-service equipment	\$15,000

Kitchen equipment total	\$120,500
-------------------------	-----------

Included in base building: kitchen plumbing/gas rough-in (Div 22), electrical rough-in (Div 26), hood curb + exhaust/MUA ductwork (Div 23), kitchen wall/floor/ceiling finishes (Div 09).

Owner cash-flow summary (Scenario A base building)

BASE BUILDING	PER GSF	PER BED (14)	PER BEDROOM (8)	PER BATHROOM (7)
\$2,318,053	\$392/SF	\$165,575	\$289,757	\$331,150

Base-building construction (excl. elevator + kitchen equip)	\$2,318,053
Separate elevator allowance	\$142,000
Separate kitchen-equipment allowance	\$120,500
All-in incl. excluded allowances	\$2,580,553

Detailed line-item breakdown — Scenario A

 shaded rows = labeled temporary allowance (no catalogue assembly). Code column shows the Kealee catalogue code or ALLOWANCE. Sub-Eq/u = subcontractor or equipment unit cost.

DIVISION 01 — General Conditions · \$252,495								
ITEM	CODE	UNIT	QTY	MAT/U	LAB/U	SUB-EQ/U	CONF	EXTENDED
Project Management – Weekly	GEN-PM-WEEKLY	each	52	\$0.00	\$805.00	—	MED	\$41,860
Site superintendent (12 mo)	ALLOWANCE	mo	12	\$0.00	\$9,500.00	—	LOW	\$114,000
Mobilization / demobilization	ALLOWANCE	ls	1	\$0.00	\$0.00	\$18,000.00	LOW	\$18,000
Temporary Power	GEN-TEMP-POWER	each	12	\$483.00	\$402.50	—	MED	\$10,626
Temporary water / heat / enclosure	ALLOWANCE	mo	12	\$0.00	\$0.00	\$850.00	LOW	\$10,200
Portable Toilet – Monthly	GEN-PORT-TOILET	each	12	\$211.31	\$0.00	—	MED	\$2,536
Safety / OSHA / PPE program	ALLOWANCE	ls	1	\$0.00	\$0.00	\$14,000.00	LOW	\$14,000
Dumpster – 30 Yard	GEN-DUMP-30	each	10	\$724.50	\$0.00	—	MED	\$7,245
Final Construction Cleanup	GEN-CLEANUP-FINAL	sqft	5,920	\$0.30	\$0.52	—	MED	\$4,854
Testing & special inspections (Type IIIB + steel)	ALLOWANCE	ls	1	\$0.00	\$0.00	\$18,000.00	LOW	\$18,000
Property Survey	GEN-SURVEY	each	1	\$724.50	\$0.00	—	MED	\$725
Structural Engineering	GEN-ENGINEER	each	1	\$1,449.00	\$0.00	—	MED	\$1,449
Closeout / as-builts / O&M / commissioning	ALLOWANCE	ls	1	\$0.00	\$0.00	\$9,000.00	LOW	\$9,000
DIVISION 02 — Existing Conditions · \$33,000								
ITEM	CODE	UNIT	QTY	MAT/U	LAB/U	SUB-EQ/U	CONF	EXTENDED
Clearing & site preparation	ALLOWANCE	ls	1	\$0.00	\$0.00	\$12,000.00	LOW	\$12,000
Erosion & sediment control (DOEE/SWM)	ALLOWANCE	ls	1	\$0.00	\$0.00	\$9,000.00	LOW	\$9,000
New rear areaway excavation/retaining	ALLOWANCE	ls	1	\$0.00	\$0.00	\$12,000.00	LOW	\$12,000
DIVISION 03 — Concrete · \$149,628								
ITEM	CODE	UNIT	QTY	MAT/U	LAB/U	SUB-EQ/U	CONF	EXTENDED
Concrete Footer	FOUND-FOOTER-NEW	lf	176	\$26.56	\$32.20	—	MED	\$10,342
Foundation wall — 8" CIP (form+rebar+pour+strip)	ALLOWANCE	sqft	1,584	\$8.50	\$6.80	\$18.70	LOW	\$53,856
Concrete Pour – 4\	CONC-POUR-4	sqft	1,480	\$5.43	\$4.60	—	MED	\$14,844
Rebar Placement	CONC-REBAR	sqft	1,480	\$1.21	\$1.44	—	MED	\$3,922
Elevator pit (excavate/form/pour/waterproof)	ALLOWANCE	ea	1	\$0.00	\$0.00	\$9,500.00	LOW	\$9,500
Exterior concrete (rear areaway, stoop, steps)	ALLOWANCE	sqft	400	\$6.00	\$3.60	\$14.40	LOW	\$9,600
Exterior Waterproofing	FOUND-WP-EXT	lf	176	\$120.75	\$149.50	—	MED	\$47,564
DIVISION 04 — Masonry · \$25,995								
ITEM	CODE	UNIT	QTY	MAT/U	LAB/U	SUB-EQ/U	CONF	EXTENDED
Brick Veneer	SID-BRICK-VEN	sqft	670	\$14.49	\$16.10	—	MED	\$20,495
Lintels, flashing, masonry accessories	ALLOWANCE	ls	1	\$0.00	\$0.00	\$5,500.00	LOW	\$5,500

DIVISION 05 — Metals (structural steel) · \$57,320								
ITEM	CODE	UNIT	QTY	MAT/U	LAB/U	SUB·EQ/U	CONF	EXTENDED
Steel Beam Installation	FOUND-STEEL-BEAM	lf	210	\$60.37	\$63.25	—	MED	\$25,960
HSS 5×5×3/8 steel columns + base/cap plates	ALLOWANCE	lf	280	\$21.70	\$9.30	\$31.00	LOW	\$17,360
Steel connections, embeds, stair/rail steel, misc metals	ALLOWANCE	ls	1	\$0.00	\$0.00	\$14,000.00	LOW	\$14,000
DIVISION 06 — Wood, Plastics & Rough Carpentry · \$176,354								
ITEM	CODE	UNIT	QTY	MAT/U	LAB/U	SUB·EQ/U	CONF	EXTENDED
Floor System – I-Joist (TJI)	FRAME-FL00R-TJI	sqft	4,440	\$7.59	\$5.17	—	MED	\$56,654
Subfloor Sheathing	FRAME-SHEATH-SUB	sqft	4,440	\$2.85	\$2.30	—	MED	\$22,866
Exterior Wall – 2x6	FRAME-WALL-2X6	lf	528	\$11.38	\$14.95	—	MED	\$13,902
Interior Wall – 2x4	FRAME-WALL-2X4	lf	1,100	\$7.59	\$11.50	—	MED	\$20,999
Wall Sheathing – OSB/Plywood	FRAME-SHEATH-WALL	sqft	5,280	\$1.90	\$2.01	—	MED	\$20,645
Low-slope roof framing (PT 2x8 @24" + steel)	ALLOWANCE	sqft	1,480	\$3.75	\$3.75	—	LOW	\$11,100
Roof Sheathing – OSB/Plywood	FRAME-SHEATH-ROOF	sqft	1,480	\$2.02	\$2.30	—	MED	\$6,394
Stair Framing	FRAME-STAIR	each	4	\$181.13	\$402.50	—	MED	\$2,335
Elevator shaft framing & 2-hr rated enclosure	ALLOWANCE	ea	1	\$0.00	\$0.00	\$14,000.00	LOW	\$14,000
Blocking, backing, misc rough carpentry	ALLOWANCE	sqft	5,920	\$0.63	\$0.63	—	LOW	\$7,459
DIVISION 07 — Thermal, Moisture & Exterior · \$116,286								
ITEM	CODE	UNIT	QTY	MAT/U	LAB/U	SUB·EQ/U	CONF	EXTENDED
Batt Insulation – R-13/R-15	FRAME-INSUL-BATT	sqft	5,280	\$0.97	\$0.98	—	MED	\$10,296
Fiber Cement Siding – Lap	SID-FC-LAP	sqft	4,700	\$6.64	\$6.90	—	MED	\$63,638
Roof / rigid insulation + air/vapor barrier	ALLOWANCE	sqft	1,480	\$1.57	\$1.13	\$1.80	LOW	\$6,660
House wrap / weather-resistive barrier	ALLOWANCE	sqft	5,280	\$0.68	\$0.68	—	LOW	\$7,181
TPO Flat Roof	R00F-FLAT-TP0	sq	14.8	\$332.06	\$276.00	—	MED	\$8,999
Gutters, downspouts, flashing, coping	ALLOWANCE	ls	1	\$0.00	\$0.00	\$8,500.00	LOW	\$8,500
Firestopping / rated assemblies (Type IIIB)	ALLOWANCE	sqft	5,920	\$0.22	\$0.22	\$0.66	LOW	\$6,512
Sealants & caulking	ALLOWANCE	ls	1	\$0.00	\$0.00	\$4,500.00	LOW	\$4,500
DIVISION 08 — Openings · \$69,989								
ITEM	CODE	UNIT	QTY	MAT/U	LAB/U	SUB·EQ/U	CONF	EXTENDED
Interior Door – Solid Core	D00R-INT-SOLID	each	40	\$362.25	\$230.00	—	MED	\$23,690
Exterior Door – Steel	D00R-EXT-STEEL	each	4	\$724.50	\$402.50	—	MED	\$4,508
Vinyl Double-Hung Window	WIN-VIN-DH	each	35	\$452.81	\$287.50	—	MED	\$25,911
Storefront / WELCOME entry glazing	ALLOWANCE	ls	1	\$0.00	\$0.00	\$9,500.00	LOW	\$9,500
Commercial hardware (levers, closers, panic)	ALLOWANCE	ea	44	\$101.50	\$43.50	—	LOW	\$6,380
DIVISION 09 — Finishes · \$197,171								
ITEM	CODE	UNIT	QTY	MAT/U	LAB/U	SUB·EQ/U	CONF	EXTENDED
Drywall Hang – Standard 1/2\	DRY-HANG-STD	sqft	20,000	\$0.70	\$1.15	—	MED	\$37,000
Drywall Tape & Finish – Level 4	DRY-TAPE-L4	sqft	20,000	\$0.30	\$1.26	—	MED	\$31,200

DIVISION 09 — Finishes · \$197,171								
ITEM	CODE	UNIT	QTY	MAT/U	LAB/U	SUB·EQ/U	CONF	EXTENDED
Rated shaft/corridor drywall upgrade (Type X)	ALLOWANCE	sqft	3,500	\$0.44	\$0.66	—	LOW	\$3,850
Suspended ACT ceilings (cellar/kitchen/support)	ALLOWANCE	sqft	1,600	\$2.16	\$1.44	\$3.60	LOW	\$11,520
Porcelain Floor Tile	FLR-TILE-PORC	sqft	900	\$9.66	\$11.50	—	MED	\$19,044
Luxury Vinyl Plank (LVP)	FLR-LVP	sqft	4,500	\$4.83	\$3.74	—	MED	\$38,565
Interior Wall Paint	PAINT-INT-WALL	sqft	20,000	\$0.48	\$1.55	—	MED	\$40,600
Finish carpentry — base, casing, trim	ALLOWANCE	sqft	5,920	\$1.04	\$1.56	—	LOW	\$15,392
DIVISION 10 — Specialties · \$14,134								
ITEM	CODE	UNIT	QTY	MAT/U	LAB/U	SUB·EQ/U	CONF	EXTENDED
ADA Grab Bar	BATH-ACC-GRAB	each	21	\$72.45	\$97.75	—	MED	\$3,574
Toilet accessories sets (7 baths)	ALLOWANCE	ea	7	\$154.00	\$66.00	—	LOW	\$1,540
Signage — egress / ADA / room ID	ALLOWANCE	ls	1	\$0.00	\$0.00	\$4,200.00	LOW	\$4,200
Fire extinguishers & cabinets	ALLOWANCE	ea	8	\$132.00	\$33.00	—	LOW	\$1,320
Misc specialties (lockers, mail, corner guards)	ALLOWANCE	ls	1	\$0.00	\$0.00	\$3,500.00	LOW	\$3,500
DIVISION 12 — Furnishings (built-in) · \$22,339								
ITEM	CODE	UNIT	QTY	MAT/U	LAB/U	SUB·EQ/U	CONF	EXTENDED
Standard Vanity with Top	BATH-VAN-STD	each	7	\$603.75	\$287.50	—	MED	\$6,239
Common/kitchen casework & countertops (base-bldg)	ALLOWANCE	lf	40	\$84.00	\$36.00	\$120.00	LOW	\$9,600
Closet/pantry shelving & built-ins (WICs 205/207)	ALLOWANCE	ls	1	\$0.00	\$0.00	\$6,500.00	LOW	\$6,500
DIVISION 21 — Fire Suppression · \$53,980								
ITEM	CODE	UNIT	QTY	MAT/U	LAB/U	SUB·EQ/U	CONF	EXTENDED
Sprinkler system — NFPA 13, full building	ALLOWANCE	sqft	5,920	\$0.00	\$0.00	\$6.50	MED	\$38,480
Fire service / standpipe / FDC allowance	ALLOWANCE	ls	1	\$0.00	\$0.00	\$12,000.00	LOW	\$12,000
Sprinkler testing & certification	ALLOWANCE	ls	1	\$0.00	\$0.00	\$3,500.00	LOW	\$3,500
DIVISION 22 — Plumbing · \$93,329								
ITEM	CODE	UNIT	QTY	MAT/U	LAB/U	SUB·EQ/U	CONF	EXTENDED
Standard Toilet	BATH-TOIL-STD	each	7	\$332.06	\$230.00	—	MED	\$3,934
Lavatories / sinks (7 baths + common + kitchen)	ALLOWANCE	ea	12	\$186.00	\$93.00	\$341.00	LOW	\$7,440
Standard Bathtub	BATH-TUB-STD	each	7	\$483.00	\$575.00	—	MED	\$7,406
DWV + water supply distribution (by fixture)	ALLOWANCE	ea	36	\$190.00	\$285.00	\$475.00	LOW	\$34,200
Gas Line – New Run	PLUMB-GAS-LINE	lf	180	\$14.49	\$23.00	—	MED	\$6,748
Water heaters — commercial (2 × WH-1)	ALLOWANCE	ea	2	\$1,680.00	\$420.00	\$2,100.00	LOW	\$8,400
Laundry rough-in + sump pump	ALLOWANCE	ls	1	\$480.00	\$800.00	\$1,920.00	LOW	\$3,200
Commercial-kitchen plumbing/gas rough-in (base-bldg)	ALLOWANCE	ls	1	\$0.00	\$0.00	\$22,000.00	MED	\$22,000

DIVISION 23 — HVAC · \$101,371								
ITEM	CODE	UNIT	QTY	MAT/U	LAB/U	SUB·EQ/U	CONF	EXTENDED
Split HVAC systems — 4 zones (CU-1..4 + AHU-1..4)	ALLOWANCE	ea	4	\$3,920.00	\$980.00	\$4,900.00	LOW	\$39,200
Ductwork distribution	ALLOWANCE	lf	900	\$6.60	\$4.40	\$11.00	LOW	\$19,800
Controls / thermostats / zoning	ALLOWANCE	ls	1	\$0.00	\$0.00	\$7,500.00	LOW	\$7,500
Bathroom Exhaust Fan – Standard	BATH - VENT - STD	each	7	\$108.67	\$230.00	—	MED	\$2,371
Kitchen hood curb, exhaust (KEF-1) & make-up air (MAU-1) ductwork (base-bldg)	ALLOWANCE	ls	1	\$0.00	\$0.00	\$26,000.00	MED	\$26,000
Elevator machine-room mini-split + TAB	ALLOWANCE	ls	1	\$0.00	\$0.00	\$6,500.00	LOW	\$6,500
DIVISION 26 — Electrical · \$139,491								
ITEM	CODE	UNIT	QTY	MAT/U	LAB/U	SUB·EQ/U	CONF	EXTENDED
Panel Upgrade – 400A	ELEC - PNL - 400	each	1	\$4,226.25	\$4,600.00	—	MED	\$8,826
Panel Upgrade – 200A	ELEC - PNL - 200	each	2	\$1,690.50	\$2,300.00	—	MED	\$7,981
Feeders & branch wiring (building-wide)	ALLOWANCE	sqft	5,920	\$3.32	\$2.38	\$3.80	LOW	\$56,240
Lighting package (LED recessed/surface, interior/exterior)	ALLOWANCE	sqft	5,920	\$1.68	\$0.84	\$1.68	LOW	\$24,864
Wiring devices & plates	ALLOWANCE	ea	220	\$16.80	\$25.20	—	LOW	\$9,240
HVAC power / equipment connections (CU/AHU/MAU/KEF)	ALLOWANCE	ea	10	\$260.00	\$390.00	—	LOW	\$6,500
Commercial-kitchen & walk-in electrical rough-in (base-bldg)	ALLOWANCE	ls	1	\$0.00	\$0.00	\$11,000.00	LOW	\$11,000
Elevator power rough-in, disconnect & cab-light circuit	ALLOWANCE	ls	1	\$0.00	\$0.00	\$5,200.00	LOW	\$5,200
Emergency & exit lighting (egress)	ALLOWANCE	ea	24	\$192.00	\$128.00	—	LOW	\$7,680
Smoke Detector – Hardwired	ELEC - SMOKE	each	14	\$42.26	\$97.75	—	MED	\$1,960
DIVISION 27/28 — Communications & Electronic Safety · \$36,417								
ITEM	CODE	UNIT	QTY	MAT/U	LAB/U	SUB·EQ/U	CONF	EXTENDED
Fire alarm system — addressable (R-2)	ALLOWANCE	sqft	5,920	\$0.00	\$0.00	\$2.60	MED	\$15,392
Cat6 Ethernet Drop	ELEC - CAT6	each	20	\$36.23	\$115.00	—	MED	\$3,025
Security / access control / intercom / CCTV	ALLOWANCE	ls	1	\$0.00	\$0.00	\$18,000.00	LOW	\$18,000
DIVISION 31 — Earthwork · \$55,656								
ITEM	CODE	UNIT	QTY	MAT/U	LAB/U	SUB·EQ/U	CONF	EXTENDED
Mass & foundation excavation (cellar)	ALLOWANCE	cy	550	\$0.00	\$8.40	\$12.60	LOW	\$23,100
Haul-off / spoil disposal	ALLOWANCE	cy	400	\$0.00	\$7.60	\$15.20	LOW	\$15,200
Backfill & compaction	ALLOWANCE	cy	180	\$0.00	\$10.20	\$6.80	LOW	\$6,120
Stone base / under-slab drainage	ALLOWANCE	sqft	1,480	\$1.92	\$1.28	—	LOW	\$4,736
Fine grading	ALLOWANCE	ls	1	\$0.00	\$0.00	\$6,500.00	LOW	\$6,500
DIVISION 32 — Exterior Improvements · \$32,500								
ITEM	CODE	UNIT	QTY	MAT/U	LAB/U	SUB·EQ/U	CONF	EXTENDED
Walks, steps & entry hardscape	ALLOWANCE	sqft	500	\$4.50	\$2.70	\$10.80	LOW	\$9,000
Site drainage / area drains	ALLOWANCE	ls	1	\$0.00	\$0.00	\$9,500.00	LOW	\$9,500

DIVISION 32 — Exterior Improvements · \$32,500								
ITEM	CODE	UNIT	QTY	MAT/U	LAB/U	SUB·EQ/U	CONF	EXTENDED
Landscaping, planter & site restoration	ALLOWANCE	ls	1	\$0.00	\$0.00	\$14,000.00	LOW	\$14,000

DIVISION 33 — Utilities · \$62,000								
ITEM	CODE	UNIT	QTY	MAT/U	LAB/U	SUB·EQ/U	CONF	EXTENDED
Domestic water service & tap	ALLOWANCE	ls	1	\$0.00	\$0.00	\$18,000.00	LOW	\$18,000
Sanitary sewer service & connection	ALLOWANCE	ls	1	\$0.00	\$0.00	\$20,000.00	LOW	\$20,000
Gas service & meter	ALLOWANCE	ls	1	\$0.00	\$0.00	\$9,000.00	LOW	\$9,000
Electrical service lateral / transformer coord (Pepco)	ALLOWANCE	ls	1	\$0.00	\$0.00	\$15,000.00	LOW	\$15,000

Kealee Platform · Estimate generated from packages/estimating catalogue (MARKETPLACE_ASSEMBLIES, DC-Baltimore 2024-25, DC region factor 1.15) and cross-checked against the Construction Task Catalog (data/ctc, DMV-2026). Planning-grade estimate: quantities assumed/calculated (no measured takeoff), ±25–35% likely until a drawing-based takeoff is performed. Not a bid. Elevator and commercial-kitchen equipment excluded from all base totals and scheduled separately.