



KEALEE

Design, build, deliver

PROJECT
1611 N KENILWORTH ST, ARLINGTON, VA, 22205
ADDRESS
1611 N KENILWORTH ST, ARLINGTON, VA, 22205
JURISDICTION
Arlington County, Virginia
ZONE
R-6
SHEET
C-100 — Existing Conditions and Boundary Plan
SCALE
1" = 20'
STATUS
PRELIMINARY
SHEET NO.
1 OF 5
COORDINATES
EPSG:2248
H: NAD83
V: NAVD88 (feet)

PROFESSIONAL RESPONSIBILITY
Virginia Licensed Surveyor
certifies: boundary_determination, topographic_survey

SEAL AND SIGNATURE

All content on this sheet falls within one professional scope.

PLAN TYPE AND PREPARATION

PLAN TYPE SITE DEVELOPMENT / FINE GRADING
SHEET C-100 — Existing Conditions and Boundary Plan
DISCIPLINE Virginia Licensed Surveyor
DRAWN BY KEALEE SITE-PLAN ENGINE
DESIGNED BY
CHECKED BY

REVISIONS

NO.	DATE	DESCRIPTION

SITE DATA	
ZONE	R-6
TAX / PARCEL ID	09023002
GROSS TRACT AREA	8,042 SF 0.185 AC
LOT FRONTAGE	— 71.08'
SETBACKS	REQUIRED PROVIDED
FRONT YARD	25' 25'
SIDE YARD	10' 10'
REAR YARD	25' 25'
COVERAGE	MAX PROPOSED
LOT COVERAGE	40% 14.9%
BUILDING FOOTPRINT	— 1,200 SF
DATUM	
HORIZONTAL	EPSG:2248 NAD83
VERTICAL	NAVD88 (feet)

SITE ANALYSIS

1. Gross tract area	8,042 SF
2. Area of dwelling	1,200 SF
3. Wooded area	NOT ESTABLISHED
4. Floodplain area	NOT ESTABLISHED
5. Net lot area	8,042 SF
6. TOTAL AREA DISTURBED	6,776 SF (AT LEAST)
7. SWM REVIEW	CONFIRM WITH ARLINGTON COUNTY DES

BUILDING DATA

	G	B	FF	SF	HT	STY
1611 N KENILWORTH ST, ARLINGTON, VA, 22205	—	—	—	—	20'	2

Legend: FF finished floor - SF subfloor - HT height - STY storeys. A DASH IS NOT ZERO: the elevation has not been established and must be set from a field-run survey construction.

DRAINAGE AREA COMPUTATIONS

CATCHMENT	SF	ACRES	C
Total — 19.8% impervious	8,042	0.185	
PRE-DEVELOPMENT	SF		C
Pervious — lawn / meadow	8,042	0.25	0.25
Composite C			0.250
POST-DEVELOPMENT	SF		C
Proposed roof	1,200	0.05	0.05
Driveway and on-lot paving	389	0.05	0.05
Pervious — lawn	6,453	0.25	0.25
Composite C			0.388
Flow path	185 ft		
Flow path slope	11.9 %		
Time of concentration (Kirpich)	11.9 %		
Rainfall intensity, 10-yr	6.85 in/hr		
Peak discharge PRE, Q = CIA	0.32 cfs		
Peak discharge POST, Q = CIA	0.49 cfs		
INCREASE TO BE MANAGED	0.17 cfs		
Rv = 0.05 + 0.0091	0.2178		
Water quality volume WQv	153 cf		

Time of concentration by Kirpich over a 185 ft flow path at 11.9%, taken from the 2 ft contours across the catchment. A 5-minute floor applies.
Rainfall intensity 6.85 in/hr for the 10-year storm at a 5.0 minute duration. NOAA Atlas 14 Vol. 2 Ver. 3. PFDS point estimate, 38,8869 N 77.1364 W.
Water quality volume on a 1.0 in rainfall. Computed by the Maryland Stormwater Design Manual method for reference only. ARLINGTON COUNTY DES's own stormwater method governs this lot.
Runoff coefficients: roof and pavement 0.05, average lawn 0.25. Confirm the lawn coefficient against the soil hydrologic group before relying on the composite.
Sidewalk, curb and gutter and the driveway apron lie in the public right-of-way and drain to the street. They are excluded from the lot catchment and included in the disturbed area.

SEQUENCE OF CONSTRUCTION

1. Pre-construction meeting
2. Obtain necessary permits
3. Notify Miss Utility at 811 at least 48 hours prior to any excavation
4. Install stabilized construction entrance and perimeter sediment control
5. Rough grade the lot
6. Construct dwelling
7. Install water, sewer and storm services and the driveway
8. Fine grade and stabilize all disturbed areas
9. Remove sediment control once the inspector gives written permission

TOTAL ESTIMATED TIME OF CONSTRUCTION: 8 MONTHS

GENERAL NOTES

1. CONTRACTOR SHALL CONTACT MISS UTILITY AT 811 A MINIMUM OF 48 HOURS PRIOR TO ANY EXCAVATION, FIELD-VERIFY LOCATION AND DEPTH BY TEST PIT BEFORE CONSTRUCTION.
2. EXISTING UTILITIES ARE SHOWN FROM PUBLIC RECORD AND ARE APPROXIMATE. LOCATION AND DEPTH SHALL BE FIELD-VERIFIED BY TEST PIT BEFORE CONSTRUCTION.
3. PROPOSED GRADE SHOWN SOLID; EXISTING GRADE SHOWN DASHED.
4. ROUGH EARTHWORK GRADES AND UTILITY ELEVATIONS SHOWN TO TENTHS OF A FOOT.
5. BOUNDARY SHOWN IS COMPILED JURISDICTION GIS, NOT A BOUNDARY SURVEY.
6. CONNECT TO EXISTING PAVEMENT, CURB AND GUTTER, DRIVEWAY AND SIDEWALK IN LINE AND GRADE.
7. NO DRIVEWAY CULVERT IS REQUIRED. THIS FRONTAGE IS AN EXISTING CURB AND GUTTER SECTION, NOT AN OPEN DITCH SECTION. GUTTER FLOW IS CARRIED THROUGH EACH ENTRANCE BY THE DEPRESSED CURB AT THE APRON PER ARLINGTON COUNTY STANDARD. ON-LOT DRAINAGE IS COLLECTED BY THE REAR-YARD SWALE IN THE REAR DRAINAGE EASEMENT AND CROSSES NO DRIVEWAY OR APRON.

PROFESSIONAL CERTIFICATION

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE COMMONWEALTH OF VIRGINIA.

SIGNATURE

DATE

SEAL

LICENSE NO.

EXPIRATION DATE

REVISIONS

— NONE —

SOILS TABLE — USDA NRCS SSURGO — survey area VA013, Arlington County

MAP UNIT	MAP UNIT NAME	K-FACT	HYDRIC	HYD. GRP	DRAINAGE CLASS
10B	Urban land-Glenelg complex, 3 to 8 percent slopes	32	No	B	Well drained
10C	Urban land-Glenelg complex, 8 to 15 percent slopes	—	Unranked	—	—
10D	Urban land-Glenelg complex, 15 to 25 percent slopes	32	No	B	Well drained
11B	Urban land-Sassafras complex, 3 to 8 percent slopes	17	No	B	Well drained

SOURCE AND ACCURACY
Jurisdiction gis — Arlington County — real estate property polygons — level 1
Existing contours — U.S. Geological Survey — 3D Elevation Program — 3DEP bare-earth DEM —...

GRAPHIC SCALE — 1" = 20'





KEALEE

Design, build, deliver

PROJECT
1611 N KENILWORTH ST, ARLINGTON, VA, 22205
ADDRESS
1611 N KENILWORTH ST, ARLINGTON, VA, 22205
JURISDICTION
Arlington County, Virginia
ZONE
R-6
SHEET
C-200 — Overall Site and Zoning Plan
SCALE
1" = 20'
STATUS
PRELIMINARY
SHEET NO.
2 OF 5
COORDINATES
EPSG:2248
H: NAD83
V: NAVD88 (feet)

PROFESSIONAL RESPONSIBILITY
Virginia Professional Engineer
certifies: Site layout

SEAL AND SIGNATURE

Architect
certifies: architectural_footprint

SEAL AND SIGNATURE

This sheet carries content from more than one professional discipline. Each seal below applies only to the subjects listed beside it. No professional certifies content outside their stated scope, and the sheet is not divided into separate drawings for that purpose.

PLAN TYPE AND PREPARATION

PLANTYPE SITE DEVELOPMENT / FINE GRADING
SHEET C-200 — Overall Site and Zoning Plan
DISCIPLINE Virginia Professional Engineer
DRAWN BY KEALEE SITE-PLAN ENGINE
DESIGNED BY
CHECKED BY

REVISIONS

NO.	DATE	DESCRIPTION

SITE DATA

ZONE	R-6
TAX / PARCEL ID	09023002
GROSS TRACT AREA	8,042 SF 0.185 AC
LOT FRONTAGE	71.08'
SETBACKS	REQUIRED PROVIDED
FRONT YARD	25' 25'
SIDE YARD	10' 10'
REAR YARD	25' 25'
COVERAGE	MAX PROPOSED
LOT COVERAGE	40% 14.9%
BUILDING FOOTPRINT	1,200 SF
DATUM	
HORIZONTAL	EPSG:2248 NAD83
VERTICAL	NAVD88 (feet)

SITE ANALYSIS

1. Gross tract area	8,042 SF
2. Area of dwelling	1,200 SF
3. Wooded area	NOT ESTABLISHED
4. Floodplain area	NOT ESTABLISHED
5. Net lot area	8,042 SF
6. TOTAL AREA DISTURBED	6,776 SF (AT LEAST)
7. SWM REVIEW	CONFIRM WITH ARLINGTON COUNTY DES

BUILDING DATA

	G	B	FF	SF	HT	STY
1611 N KENILWORTH ST, ARLINGTON, VA, 22205	—	—	—	—	20'	2

DRAINAGE AREA COMPUTATIONS

CATCHMENT	SF	ACRES	C
Total — 12.8% impervious	8,042	0.185	
PRE-DEVELOPMENT	SF		C
Previous — lawn / meadow	8,042		0.25
Composite C			0.250
POST-DEVELOPMENT	SF		C
Proposed roof	1,200		0.95
Driveway and on-lot paving	389		0.95
Previous — lawn	6,453		0.25
Composite C			0.388
Flow path			185 ft
Flow path slope			11.9 %
Time of concentration (Kirpich)			5.0 min
Rainfall intensity, 10-yr			6.85 in/hr
Peak discharge PRE, Q = CIA			0.32 cfs
Peak discharge POST, Q = CIA			0.49 cfs
INCREASE TO BE MANAGED			0.17 cfs
Rv = 0.05 + 0.008 I			0.2278
Water quality volume WQv			153 cf

Time of concentration by Kirpich over a 185 ft flow path at 11.9%, taken from the 2 ft contours across the catchment. A 5-minute floor applies.
Rainfall intensity 6.85 in/hr for the 10-year storm at a 5.0 minute duration, NOAA Atlas 14 Vol. 2 Ver. 3, PFDS point estimate, 38 8869 N 77 1364 W.
Water quality volume on a 1.0 in rainfall. Computed by the Maryland Stormwater Design Manual method for reference only. ARLINGTON COUNTY DES's own stormwater method governs this lot.
Runoff coefficients: roof and pavement 0.95, average lawn 0.25. Confirm the lawn coefficient against the soil hydrologic group before relying on the composite.
Sidewalk, curb and gutter and the driveway apron lie in the public right-of-way and drain to the street. They are excluded from the lot catchment and included in the disturbed area.

SEQUENCE OF CONSTRUCTION

1. Pre-construction meeting	1 DAY
2. Obtain necessary permits	2 DAYS
3. Notify Miss Utility at 811 at least 48 hours prior to any excavation	1 DAY
4. Install stabilized construction entrance and perimeter sediment control	2 DAYS
5. Rough grade the lot	5 DAYS
6. Construct dwelling	6 MONTHS
7. Install water, sewer and storm services and the driveway	10 DAYS
8. Fine grade and stabilize all disturbed areas	5 DAYS
9. Remove sediment control once the inspector gives written permission	1 DAY

TOTAL ESTIMATED TIME OF CONSTRUCTION: 8 MONTHS

LEGEND

— — —	PROPERTY BOUNDARY
— — —	BRL — BUILDING RESTRICTION LINE
— — —	PROPOSED STRUCTURE
— — —	EXISTING CONTOUR — 2 FT INTERVAL, NAVD88
— — —	PROPOSED CONTOUR — 2 FT INTERVAL
— — —	STREET CENTRELINE
— — —	PROPOSED PAVEMENT — DRIVEWAY / WALK
— — —	EASEMENT
— — —	SANITARY LATERAL (SHC) — HEAVIEST
— — —	WATER SERVICE (WHC)
— — —	STORM DRAIN — TRUNK, RCP
— — —	STORM — HOUSE CONNECTION TO TRUNK
— — —	DRAINAGE SWALE — INVERT AND GRADED SECTION
— — —	RETAINING WALL — TICKS ON THE RETAINED SIDE
— — —	LIMIT OF GROUND COVER — TICKS ON THE STEEP SIDE
— — —	ESD — STORMWATER PRACTICE

PROFESSIONAL CERTIFICATION

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE COMMONWEALTH OF VIRGINIA.

SIGNATURE

DATE

SEAL

LICENSE NO.

EXPIRATION DATE

REVISIONS

— NONE —

SOILS STABLE — USDA NRCS SSURGO — survey area VA013, Arlington County

MAP UNIT	MAP UNIT NAME	K-FACT	HYDRIC	HYD. GRP	DRAINAGE CLASS
10B	Urban land-Glenelg complex, 3 to 8 percent slopes	32	No	B	Well drained
10C	Urban land-Glenelg complex, 8 to 15 percent slopes	—	Unranked	—	—
10D	Urban land-Glenelg complex, 15 to 25 percent slopes	32	No	B	Well drained
11B	Urban land-Sassafras complex, 3 to 8 percent slopes	17	No	B	Well drained

SOURCE AND ACCURACY
Parcel boundary — Jurisdiction gis — Arlington County — real estate property polygons — level 1
Existing contours — U.S. Geological Survey — 3D Elevation Program — 3DEP bare-earth DEM —...

GRAPHIC SCALE — 1" = 20'

0 20 40 60 80 FEET



KEALEE

Design, build, deliver

PROJECT
1611 N KENILWORTH ST, ARLINGTON, VA, 22205
ADDRESS
1611 N KENILWORTH ST, ARLINGTON, VA, 22205
JURISDICTION
Arlington County, Virginia
ZONE
R-6
SHEET
C-400 — Grading and Drainage Plan
SCALE
1" = 20'
STATUS
PRELIMINARY
SHEET NO.
3 OF 5
COORDINATES
EPSG:2248
H: NAD83
V: NAVD88 (feet)

PROFESSIONAL RESPONSIBILITY
Virginia Professional Engineer
certifies: grading_design, sediment_control, stormwater_design

SEAL AND SIGNATURE

All content on this sheet falls within one professional scope.

PLAN TYPE AND PREPARATION

PLAN TYPE SITE DEVELOPMENT / FINE GRADING
SHEET C-400 — Grading and Drainage Plan
DISCIPLINE Virginia Professional Engineer
DRAWN BY KEALEE SITE-PLAN ENGINE
DESIGNED BY
CHECKED BY

REVISIONS

NO.	DATE	DESCRIPTION

SITE DATA

ZONE	R-6
TAX / PARCEL ID	09023002
GROSS TRACT AREA	8,042 SF 0.185 AC
LOT FRONTAGE	— 71.08'
SETBACKS	REQUIRED PROVIDED
FRONT YARD	25' 25'
SIDE YARD	10' 10'
REAR YARD	25' 25'
COVERAGE	MAX PROPOSED
LOT COVERAGE	40% 14.9%
BUILDING FOOTPRINT	— 1,200 SF
DATUM	
HORIZONTAL	EPSG:2248 NAD83
VERTICAL	NAVD88 (feet)

SITE ANALYSIS

1. Gross tract area	8,042 SF
2. Area of dwelling	1,200 SF
3. Wooded area	NOT ESTABLISHED
4. Floodplain area	NOT ESTABLISHED
5. Net lot area	8,042 SF
6. TOTAL AREA DISTURBED	6,776 SF (AT LEAST)
7. SWM REVIEW	CONFIRM WITH ARLINGTON COUNTY DES

BUILDING DATA

	G	B	FF	SF	HT	STY
1611 N KENILWORTH ST, ARLINGTON, VA, 22205	—	—	—	—	20'	2

1611 N KENILWORTH ST, ARLINGTON, VA, 22205
Subsistence: FF finished floor - SF subfloor - HT height - STY storeys. A DASH IS NOT ZERO; the elevation has not been established and must be set from a field-run survey construction.

DRAINAGE AREA COMPUTATIONS

CATCHMENT	SF	ACRES	C
Total — 19.8% impervious	8,042	0.185	
PRE-DEVELOPMENT	SF		C
Pervious — lawn / meadow	8,042		0.25
Composite C			0.250
POST-DEVELOPMENT	SF		C
Proposed roof	1,200		0.95
Driveway and on-lot paving	389		0.95
Pervious — lawn	6,453		0.25
Composite C			0.388
Flow path			185 ft
Flow path slope			11.9 %
Time of concentration (Kirpich)			5.0 min
Rainfall intensity, 10-yr			6.85 in/hr
Peak discharge PRE, Q = CIA			0.32 cfs
Peak discharge POST, Q = CIA			0.49 cfs
INCREASE TO BE MANAGED			0.17 cfs
Rv = 0.05 + 0.0091			0.2178
Water quality volume WQv			153 cf

Time of concentration by Kirpich over a 185 ft flow path at 11.9%, taken from the 2 ft contours across the catchment. A 5-minute floor applies.
Rainfall intensity 6.85 in/hr for the 10-year storm at a 5.0 minute duration, NOAA Atlas 14 Vol. 2, Ver. 3, PF05D point estimate, 38,8869 N 77.1364 W.
Water quality volume on a 1.0 in rainfall. Computed by the Maryland Stormwater Design Manual method for reference only. ARLINGTON COUNTY DES's own stormwater method governs this lot.
Runoff coefficients: roof and pavement 0.95, average lawn 0.25. Confirm the lawn coefficient against the soil hydrologic group before relying on the composite.
Sidewalk, curb and gutter and the driveway apron lie in the public right-of-way and drain to the street. They are excluded from the lot catchment and included in the disturbed area.

SEQUENCE OF CONSTRUCTION

1. Pre-construction meeting
2. Obtain necessary permits
3. Notify Miss Utility at 811 at least 48 hours prior to any excavation
4. Install stabilized construction entrance and perimeter sediment control
5. Rough grade the lot
6. Construct dwelling
7. Install water, sewer and storm services and the driveway
8. Fine grade and stabilize all disturbed areas
9. Remove sediment control once the inspector gives written permission

TOTAL ESTIMATED TIME OF CONSTRUCTION: 8 MONTHS

GENERAL NOTES

1. CONTRACTOR SHALL CONTACT MISS UTILITY AT 811 A MINIMUM OF 48 HOURS PRIOR TO ANY EXCAVATION, FIELD-VERIFY LOCATION AND DEPTH BY TEST PIT BEFORE CONSTRUCTION.
2. EXISTING UTILITIES ARE SHOWN FROM PUBLIC RECORD AND ARE APPROXIMATE. LOCATION AND DEPTH SHALL BE FIELD-VERIFIED BY TEST PIT BEFORE CONSTRUCTION.
3. PROPOSED GRADE SHOWN SOLID; EXISTING GRADE SHOWN DASHED.
4. ROUGH EARTHWORK GRADES AND UTILITY ELEVATIONS SHOWN TO TENTHS OF A FOOT.
5. BOUNDARY SHOWN IS COMPILED JURISDICTION GIS, NOT A BOUNDARY SURVEY.
6. CONNECT TO EXISTING PAVEMENT, CURB AND GUTTER, DRIVEWAY AND SIDEWALK IN LINE AND GRADE.
7. NO DRIVEWAY CULVERT IS REQUIRED. THIS FRONTAGE IS AN EXISTING CURB AND GUTTER SECTION, NOT AN OPEN DITCH SECTION. GUTTER FLOW IS CARRIED THROUGH EACH ENTRANCE BY THE DEPRESSED CURB AT THE APRON PER ARLINGTON COUNTY STANDARD. ON-LOT DRAINAGE IS COLLECTED BY THE REAR-YARD SWALE IN THE REAR DRAINAGE EASEMENT AND CROSSES NO DRIVEWAY OR APRON.

PROFESSIONAL CERTIFICATION

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE COMMONWEALTH OF VIRGINIA.

SIGNATURE

DATE

SEAL

LICENSE NO.

EXPIRATION DATE

REVISIONS

— NONE —

SOILS TABLE

USDA NRCS SSURGO — survey area VA013, Arlington County

MAP UNIT	MAP UNIT NAME	K-FACT	HYDRIC	HYD. GRP	DRAINAGE CLASS
10B	Urban land-Glenelg complex, 3 to 8 percent slopes	32	No	B	Well drained
10C	Urban land-Glenelg complex, 8 to 15 percent slopes	—	Unranked	—	—
10D	Urban land-Glenelg complex, 15 to 25 percent slopes	32	No	B	Well drained
11B	Urban land-Sassafras complex, 3 to 8 percent slopes	17	No	B	Well drained

SOURCE AND ACCURACY
Parcel boundary — Jurisdiction gis — Arlington County — real estate property polygons — level 1
Existing contours — U.S. Geological Survey — 3D Elevation Program — 3DEP bare-earth DEM —

GRAPHIC SCALE — 1" = 20'

0 20 40 60 80 FEET



KEALEE

Design, build, deliver

PROJECT
1611 N KENILWORTH ST, ARLINGTON, VA, 22205
ADDRESS
1611 N KENILWORTH ST, ARLINGTON, VA, 22205
JURISDICTION
Arlington County, Virginia
ZONE
R-6
SHEET
C-500 — Utility Plan
SCALE
1" = 20'
STATUS
PRELIMINARY
SHEET NO.
4 OF 5
COORDINATES
EPSG:2248
H: NAD83
V: NAVD88 (feet)
PROFESSIONAL RESPONSIBILITY
Virginia Professional Engineer
certifies: Utility_Design

SEAL AND SIGNATURE

All content on this sheet falls within one professional scope.

PLAN TYPE AND PREPARATION

PLAN TYPE SITE DEVELOPMENT / FINE GRADING
SHEET C-500 — Utility Plan
DISCIPLINE Virginia Professional Engineer
DRAWN BY KEALEE SITE-PLAN ENGINE
DESIGNED BY
CHECKED BY

REVISIONS

NO.	DATE	DESCRIPTION

SITE DATA	
ZONE	R-6
TAX / PARCEL ID	09023002
GROSS TRACT AREA	8,042 SF 0.185 AC
LOT FRONTAGE	— 71.08'
SETBACKS	REQUIRED PROVIDED
FRONT YARD	25' 25'
SIDE YARD	10' 10'
REAR YARD	25' 25'
COVERAGE	MAX PROPOSED
LOT COVERAGE	40% 14.9%
BUILDING FOOTPRINT	— 1,200 SF
DATUM	
HORIZONTAL	EPSG:2248 NAD83
VERTICAL	NAVD88 (feet)

SITE ANALYSIS

1. Gross tract area	8,042 SF
2. Area of dwelling	1,200 SF
3. Wooded area	NOT ESTABLISHED
4. Floodplain area	NOT ESTABLISHED
5. Net lot area	8,042 SF
6. TOTAL AREA DISTURBED	6,776 SF (AT LEAST)
7. SWM REVIEW	CONFIRM WITH ARLINGTON COUNTY DES

BUILDING DATA

	G	B	FF	SF	HT	STY
1611 N KENILWORTH ST, ARLINGTON, VA, 22205	—	—	—	—	20'	2

1611 N KENILWORTH ST, ARLINGTON, VA, 22205
Legend: FF finished floor - SF subfloor - HT height - STY storeys. A DASH IS NOT ZERO: the elevation has not been established and must be set from a field-run before construction.

DRAINAGE AREA COMPUTATIONS

CATCHMENT	SF	ACRES	C
Total — 19.8% impervious	8,042	0.185	
PRE-DEVELOPMENT	SF		C
Pervious — lawn / meadow	8,042	0.25	0.250
Composite C	SF		C
POST-DEVELOPMENT	SF		C
Proposed roof	1,200	0.05	0.05
Driveway and on-lot paving	389	0.05	0.05
Pervious — lawn	6,453	0.25	0.388
Composite C			
Flow path	185 ft		
Flow path slope	11.9 %		
Time of concentration (Kirpich)	5.0 min		
Rainfall intensity, 10-yr	6.85 in/hr		
Peak discharge PRE, Q = CIA	0.32 cfs		
Peak discharge POST, Q = CIA	0.49 cfs		
INCREASE TO BE MANAGED	0.17 cfs		
Rv = 0.05 + 0.0091	0.2178		
Water quality volume WQv	153 cf		
Time of concentration by Kirpich over a 185 ft flow path at 11.9%, taken from the 2 ft contours across the catchment. A 5-minute floor applies. Rainfall intensity 6.85 in/hr for the 10-year storm at a 5.0 minute duration. NOAA Atlas 14 Vol. 2 Ver. 3. PF05D point estimate, 38.8869 N 77.1364 W. Water quality volume on a 1.0 in rainfall. Computed by the Maryland Stormwater Design Manual method for reference only. ARLINGTON COUNTY DES's own stormwater method governs this lot. Runoff coefficients: roof and pavement 0.05, average lawn 0.25. Confirm the lawn coefficient against the soil hydrologic group before relying on the composite. Sidewalk, curb and gutter and the driveway apron lie in the public right-of-way and drain to the street. They are excluded from the lot catchment and included in the disturbed area.			

SEQUENCE OF CONSTRUCTION

1. Pre-construction meeting
2. Obtain necessary permits
3. Notify Miss Utility at 811 at least 48 hours prior to any excavation
4. Install stabilized construction entrance and perimeter sediment control
5. Rough grade the lot
6. Construct dwelling
7. Install water, sewer and storm services and the driveway
8. Fine grade and stabilize all disturbed areas
9. Remove sediment control once the inspector gives written permission

TOTAL ESTIMATED TIME OF CONSTRUCTION: 8 MONTHS

GENERAL NOTES

1. CONTRACTOR SHALL CONTACT MISS UTILITY AT 811 A MINIMUM OF 48 HOURS PRIOR TO ANY EXCAVATION, FIELD-VERIFY LOCATION AND DEPTH BY TEST PIT BEFORE CONSTRUCTION.
2. EXISTING UTILITIES ARE SHOWN FROM PUBLIC RECORD AND ARE APPROXIMATE. LOCATION AND DEPTH SHALL BE FIELD-VERIFIED BY TEST PIT BEFORE CONSTRUCTION.
3. PROPOSED GRADE SHOWN SOLID; EXISTING GRADE SHOWN DASHED.
4. ROUGH EARTHWORK GRADES AND UTILITY ELEVATIONS SHOWN TO TENTHS OF A FOOT.
5. BOUNDARY SHOWN IS COMPILED JURISDICTION GIS, NOT A BOUNDARY SURVEY.
6. CONNECT TO EXISTING PAVEMENT, CURB AND GUTTER, DRIVEWAY AND SIDEWALK IN LINE AND GRADE.
7. NO DRIVEWAY CULVERT IS REQUIRED. THIS FRONTAGE IS AN EXISTING CURB AND GUTTER SECTION, NOT AN OPEN DITCH SECTION. GUTTER FLOW IS CARRIED THROUGH EACH ENTRANCE BY THE DEPRESSED CURB AT THE APRON PER ARLINGTON COUNTY STANDARD. ON-LOT DRAINAGE IS COLLECTED BY THE REAR-YARD SWALE IN THE REAR DRAINAGE EASEMENT AND CROSSES NO DRIVEWAY OR APRON.

PROFESSIONAL CERTIFICATION

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE COMMONWEALTH OF VIRGINIA.

SIGNATURE

DATE

SEAL

LICENSE NO.

EXPIRATION DATE

REVISIONS

— NONE —

SOILS TABLE USDA NRCS SSURGO — survey area VA013, Arlington County

MAP UNIT	MAP UNIT NAME	K-FACT	HYDRIC	HYD. GRP	DRAINAGE CLASS
10B	Urban land-Glenelg complex, 3 to 8 percent slopes	32	No	B	Well drained
10C	Urban land-Glenelg complex, 8 to 15 percent slopes	—	Unranked	—	—
10D	Urban land-Glenelg complex, 15 to 25 percent slopes	32	No	B	Well drained
11B	Urban land-Sassafras complex, 3 to 8 percent slopes	17	No	B	Well drained

SOURCE AND ACCURACY
Jurisdiction gis — Arlington County — real estate property polygons — level 1
Existing contours — U.S. Geological Survey — 3D Elevation Program — 3DEP bare-earth DEM —

GRAPHIC SCALE — 1" = 20'

0 20 40 60 80 FEET



KEALEE

Design, build, deliver

PROJECT
1611 N KENILWORTH ST, ARLINGTON, VA, 22205
ADDRESS
1611 N KENILWORTH ST, ARLINGTON, VA, 22205
JURISDICTION
Arlington County, Virginia
ZONE
R-6
SHEET
L-100 — Landscape and Tree Canopy Plan
SCALE
1" = 20'
STATUS
PRELIMINARY
SHEET NO.
5 OF 5
COORDINATES
EPSG:2248
H: NAD83
V: NAVD88 (feet)

PROFESSIONAL RESPONSIBILITY
Qualified Environmental Professional
certifies: tree_conservation

SEAL AND SIGNATURE

All content on this sheet falls within one professional scope.

PLAN TYPE AND PREPARATION

PLAN TYPE SITE DEVELOPMENT / FINE GRADING
SHEET L-100 — Landscape and Tree Canopy Plan
DISCIPLINE Landscape Architect / Qualified Professional
DRAWN BY KEALEE SITE-PLAN ENGINE
DESIGNED BY
CHECKED BY

REVISIONS

NO.	DATE	DESCRIPTION

SITE DATA	
ZONE	R-6
TAX / PARCEL ID	09023002
GROSS TRACT AREA	8,042 SF 0.185 AC
LOT FRONTAGE	— 71.08'
SETBACKS	REQUIRED PROVIDED
FRONT YARD	25' 25'
SIDE YARD	10' 10'
REAR YARD	25' 25'
COVERAGE	MAX PROPOSED
LOT COVERAGE	40% 14.9%
BUILDING FOOTPRINT	— 1,200 SF
DATUM	
HORIZONTAL	EPSG:2248 NAD83
VERTICAL	NAVD88 (feet)

SITE ANALYSIS

1. Gross tract area	8,042 SF
2. Area of dwelling	1,200 SF
3. Wooded area	NOT ESTABLISHED
4. Floodplain area	NOT ESTABLISHED
5. Net lot area	8,042 SF
6. TOTAL AREA DISTURBED	6,776 SF (AT LEAST)
7. SWM REVIEW	CONFIRM WITH ARLINGTON COUNTY DES

BUILDING DATA

	G	B	FF	SF	HT	STY
1611 N KENILWORTH ST, ARLINGTON, VA, 22205	—	—	—	—	20'	2

1611 N KENILWORTH ST, ARLINGTON, VA, 22205
Subsidence: FF finished floor - SF subfloor - HT height - STY storeys. A DASH IS NOT ZERO: the elevation has not been established and must be set from a field-run survey construction.

DRAINAGE AREA COMPUTATIONS

CATCHMENT	SF	ACRES	C
Total — 19.8% impervious	8,042	0.185	
PRE-DEVELOPMENT	SF		C
Pervious — lawn / meadow	8,042		0.25
Composite C			0.250
POST-DEVELOPMENT	SF		C
Proposed roof	1,200		0.95
Driveway and on-lot paving	389		0.95
Pervious — lawn	6,453		0.25
Composite C			0.388
Flow path			185 ft
Flow path slope			11.9 %
Time of concentration (Kirpich)			5.0 min
Rainfall intensity, 10-yr			6.85 in/hr
Peak discharge PRE, Q = CIA			0.32 cfs
Peak discharge POST, Q = CIA			0.49 cfs
INCREASE TO BE MANAGED			0.17 cfs
Rv = 0.05 + 0.0091			0.2178
Water quality volume WQv			153 cf

Time of concentration by Kirpich over a 185 ft flow path at 11.9%, taken from the 2 ft contours across the catchment. A 5-minute floor applies.
Rainfall intensity 6.85 in/hr for the 10-year storm at a 5.0 minute duration. NOAA Atlas 14 Vol. 2 Ver. 3. PFDS point estimate, 38,8869 N 77.1364 W.
Water quality volume on a 1.0 in rainfall. Computed by the Maryland Stormwater Design Manual method for reference only. ARLINGTON COUNTY DES's own stormwater method governs this lot.
Runoff coefficients: roof and pavement 0.95, average lawn 0.25. Confirm the lawn coefficient against the soil hydrologic group before relying on the composite.
Sidewalk, curb and gutter and the driveway apron lie in the public right-of-way and drain to the street. They are excluded from the lot catchment and included in the disturbed area.

SEQUENCE OF CONSTRUCTION

1. Pre-construction meeting	1 DAY
2. Obtain necessary permits	2 DAYS
3. Notify Miss Utility at 811 at least 48 hours prior to any excavation	1 DAY
4. Install stabilized construction entrance and perimeter sediment control	2 DAYS
5. Rough grade the lot	5 DAYS
6. Construct dwelling	6 MONTHS
7. Install water, sewer and storm services and the driveway	10 DAYS
8. Fine grade and stabilize all disturbed areas	5 DAYS
9. Remove sediment control once the inspector gives written permission	1 DAY

TOTAL ESTIMATED TIME OF CONSTRUCTION: 8 MONTHS

GENERAL NOTES

- CONTRACTOR SHALL CONTACT MISS UTILITY AT 811 A MINIMUM OF 48 HOURS PRIOR TO ANY EXCAVATION, FIELD-VERIFY LOCATION AND DEPTH BY TEST PIT BEFORE CONSTRUCTION.
- EXISTING UTILITIES ARE SHOWN FROM PUBLIC RECORD AND ARE APPROXIMATE. LOCATION AND DEPTH SHALL BE FIELD-VERIFIED BY TEST PIT BEFORE CONSTRUCTION.
- PROPOSED GRADE SHOWN SOLID; EXISTING GRADE SHOWN DASHED.
- ROUGH EARTHWORK GRADES AND UTILITY ELEVATIONS SHOWN TO TENTHS OF A FOOT.
- BOUNDARY SHOWN IS COMPILED JURISDICTION GIS, NOT A BOUNDARY SURVEY.
- CONNECT TO EXISTING PAVEMENT, CURB AND GUTTER, DRIVEWAY AND SIDEWALK IN LINE AND GRADE.
- NO DRIVEWAY CULVERT IS REQUIRED. THIS FRONTAGE IS AN EXISTING CURB AND GUTTER SECTION, NOT AN OPEN DITCH SECTION. GUTTER FLOW IS CARRIED THROUGH EACH ENTRANCE BY THE DEPRESSED CURB AT THE APRON PER ARLINGTON COUNTY STANDARD. ON-LOT DRAINAGE IS COLLECTED BY THE REAR-YARD SWALE IN THE REAR DRAINAGE EASEMENT AND CROSSES NO DRIVEWAY OR APRON.

PROFESSIONAL CERTIFICATION

I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE COMMONWEALTH OF VIRGINIA.

SIGNATURE

DATE

SEAL

LICENSE NO.

EXPIRATION DATE

REVISIONS

— NONE —

SOURCE AND ACCURACY
Parcel boundary — Jurisdiction gis — Arlington County — real estate property polygons — level 1
Existing contours — U.S. Geological Survey — 3D Elevation Program — 3DEP bare-earth DEM —

GRAPHIC SCALE — 1" = 20'

